

NEWAYGO COUNTY REGISTER OF DEEDS  
 MARLENE TOOGOOD  
 1993 NEWAYGO-COUNTY REMONUMENTATION PROJECT  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970, 94 JAN 21 PM 3 25

For corners in Newaygo (County) Located In: Corner Code A-3

1. Public Land Survey T 13N R 13W \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Marlene Toogood*  
**VOL 001 PAGE 20**  
 Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

SW. Corner, Section 6, Sherman Twp., Newaygo Co., Mich.

A. Description of original monument and accessories and/or subsequent restoration:

G.I.O. 1837 John Millett N.C.R.C. Sheet  
 8" Beech S85°E 21 lks. #1 2" Pipe  
 6" Beech N36°E 331ks. #2 Corner Fence Post N45°E 42.7' #3  
 Corner Fence Post N45°W 43.1' #4

5-11-39 Lyle S. Shepherd #503  
 Witness Book #2 Pg. 19 2" Pipe  
 Corner Fence Post N45°E 42.7' #3  
 Corner Fence Post N45°W 43.1' #4

March 1968 Salisbury & Sanders  
 Set 1/2" Rod from wit. for CP. #3  
 Tele. Pole S45°W 49.90' #5  
 Guy Pole S50°E 47.65' #6  
 Fence Corner Post N45°W 43.1' #6

6-17-69 Newaygo Eng. & Survey Co.  
 Set 1/2" Rod  
 P. Pole S45°E 141.45' #7  
 6" Pine S20°E 116.60' #8  
 Tele. Pole S45°W 49.85' #5  
 Fence Corner Post N45°W 43.40' #4


3-26-84 Newaygo Eng. & Survey Co.  
 Found 1/2" Rod  
 P. Pole S45°E 141.51' #7  
 P. Pole N75°E 100.25' #9  
 NE. Cor. Tel. Riser  
 S45°W 51.99' #10

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 12-03-93 found 1/2" pipe over 1/2" rod, rasised with 1/2" Rod, replaced with 4" Harrison Cast Iron Monument.  
 In 1968 Salisbury and Sanders did a section break of Sec. 7, Sherman Twp. for Consumers Power Co.. They set 1/2" rod from 1939 witnesses.

Condition of recorded witnesses is: #1 thru #6 Gone #7 Good Condition #8 Gone #9 and #10 Good Condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Accepted 4" Harrison Monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

P. Pole S38°E 141.48' spike in NE. side of pole #7  
 NE. Corner Tel Riser S50°W 51.92' NE. Cor. Conc. Base for riser #10  
 P. Pole N65°E 100.25' spike in SE side of pole #9  
 centerline of stop sign post S78°W 52.05'



Signed by Norman L. Ochs Date December 27, 1993  
 Surveyor's Michigan License No. Norman L. Ochs R.L.S. #22439  
 Approved by Peer Review Group December 27, 1993  
 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

**SURVEY & REMONUMENTATION**  
 DEC 07 2000  
 SECTION