

**SURVEY & REMONUMENTATION** 1995 Newaygo County Remonumentation Project

APR 04 1996

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

VOL. **1** PAGE **179**

NEWAYGO COUNTY  
 REGISTER OF DEEDS  
 HARLAN TOWNSHIP

FEB 21 AM 9 40

*Madeline Torgood*

For corners in **COMMISSION**  
Newaygo  
 (County)

Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>13N</u> R <u>13W</u> | <u>E-5</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                           |            |
| 5. Private Claims _____               |                           |            |

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on June 7, 1995, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

N.E. Corner, Section 17, Sherman Twp., Newaygo Co., MI

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

- |  |   |
|--|---|
| G.L.O. John Mullet 1838<br>12" Beech N44° E 18Lks (11.88")#1<br>8" Beech N35°E 34Lks (22.44")#2  | Lyle S. Shepherd RLS #503<br>Witness Book No. 2 Pg. 31<br>1943 Nothing found  |
| Delos G. Anderson (Co. Surveyor)<br>Book A Pg. 197 March 10, 1897<br>15" Pine Stp. S79°W 55Lks (36.3") #3<br>18" Pine Stp. N09°E 72LKS (47.52")#4<br>Measured 40.09 ch (2645.94 ft) from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 and measured 40.87 ch (2697.42 ft) from the N.E. Cor. to the E. ¼ Cor. of Sec. 17 | NCRC Sheet<br>½" iron<br>6" Butternut N49°W 43.5' #5<br>P. Pole S50°W 66.0' #6<br>Measured 2642.58 ft from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 and<br>Measured 2683.10 ft from the N.E. Cor. to the E. ¼ Cor. of Sec. 17 and<br>Measured 2650.75 ft from the S.E. Cor. to the E. ¼ Cor. of Sec. 8 |
| Patrick A. Salisbury RLS #13594<br>Sept. 26, 1974 Found R.R. Spike<br>10" Butternut N50°W 43.80' #5<br>P. Pole N52°E 38.10' #7<br>P. Pole S55°W 62.67' #6<br>Measured 2650.12 ft from the S.W. Cor. to the W. ¼ Cor. of Sec. 9   | Newaygo Engineering and Survey Co.<br>March 9, 1984 Drawing No. 84023B<br>Measured 2638.87 ft from the S.E. Cor. to the S. ¼ Cor. of Sec. 8 and<br>Measured 2649.42 ft from the S.E. Cor. to the E. ¼ Cor. of Sec. 8  |

OVER ↵

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found R.R. Spike. The centerline of the N-S road is 2 feet West and in the centerline of the road going West. I measured 2638.80 ft from the N. ¼ cor. to the N.E. Cor. and measured 2679.07 ft from the N.E. Cor. to the E. ¼ cor. of Sec. 17 and the condition of recorded witnesses are: #1 thru #6 gone, #7 thru #8 good condition, #9 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed R.R. Spike and set a 4" dia. Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner

- 10" Walnut N50°W 43.83' Fnd spike in Northeast side of tree. #5
- Utility Pole S53°W 62.92' Fnd spike in Southeast side of pole. #6
- Utility Pole N52°E 37.95' Fnd spike in South side of pole. #7
- ½" Iron w/cap N88°W 439.80' #8
- ½" Iron West 32.97'

Signed by Norman L. Ochs Date September 11, 1995

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 23, 1995



Approved by Peer Review Group on October 3, 1995  
 Norman L. Ochs, County Representative.

Revised May 14, 1975  
 Revised Jan., 1983

*N. L. O.*

A. Description .... (Continued)

William Fries, Jr. P.S. #30389

Found R.R. Spike LCRC #723 and see survey recorded in Series S No. 8863

P. Pole N61°E 38.07' #7

P. Pole S63°W 62.71' #6

½" iron w/cap N88°W 439.80' #8

8" Walnut N50°W 43.74' #5

Measured 2638.78 ft from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 and measured 2679.05 ft from the N.E. Cor. to the E. ¼ Cor of Sec. 17

Newaygo Engineering and Survey Co.

Drawing No. 91374B October 17, 1991

Found R.R. Spike

P. Pole N61°E 38.07' #7

P. Pole S63°W 62.71' #6

8" Walnut N50°W 43.74' #5

3" R. Pine S31°E 45.60' #9

Measured 2652.81 ft from the S.W. Cor. to the S. ¼ Cor. of Sec. 9 and measured 2649.42 ft from the S.W. Cor. to the W. ¼ Cor of Sec. 9