

SURVEY & REMONUMENTATION

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE 00 FEB 28 PM 1 17 FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>13W</u>	<u>J-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

344

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on November 3, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 11, Sherman Township, Newaygo County, Michigan.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Mullett 1838
8" Maple N58°E 22 Links (14.52') #1
10" Beech S44°E 33 Links (21.78') #2

Lyle S. Shepherd R.L.S. #503
Witness Book Number 2, Page 25
White Oak Southeast 41.3' #3
Pine Stump Southwest 41.2' #4
Pine Stump Northeast 31.8' #5

Robert A. Griffin R.L.S. #13584
1973

Measured 2625.41 feet from the Southwest Corner to the South One Quarter Corner of Section 2 and measured 2641.48 feet from the South One Quarter Corner to the Southeast Corner of Section 2.

Matt Koivisto R.L.S. #16047
October 28, 1970
Found 1/2" Pipe 2 feet below surface raised with 3/4" Iron bar.
16" Oak S25°W 68.18' #6
13" Oak S15°E 49.20' #7
24" Twin Oak N15°E 38.81' #8

David R. Greer R.L.S. #16042
June 2, 1972 LCRC #50
Found 3/4" Iron bar
16" Oak S25°W 68.18' #6
13" Oak S15°E 49.20' #7
24" Twin Oak N15°E 38.81' #8

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" x 32" Iron Pipe (in monument box prior to construction) on line ± with stump row fence going North and the centerline of the East and West bituminous road is 4 feet ± South and there is no apparent occupation going South. The condition of the recorded witnesses are: #1 thru #5 gone, #6 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Iron Pipe and set a 2 3/4" diameter Harrison cast iron monument 20" long marked "County Survey" in a new 8" diameter monument box as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

18" Black Oak (blazed) S37°W 68.24' Set spike with tag #22439 in Northwest side of tree. #6
18" White Oak (blazed) S17°E 49.23' Found spike with tag #22439 in East side of tree. #7
22" Black Oak (also 18" stump of twin - blazed) N15°E 38.70' Found spike in West side of tree. #8
14" Red Oak (blazed) N70°W 80.92' Set spike with tag #22439 (above bent spike) in Northwest side of tree.

Signed by Norman L. Ochs Date November 8, 1999

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 22, 1971

Approved by Peer Review Group on December 16, 1999
Norman L. Ochs, County Representative.

N.L.O.

