

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'99 FEB 17 PM 3 38

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 13N R 13W K-1 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

Linda M. Brown

VOL. 2

221

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Cell (1, K) is shaded.

I, Norman L. Ochs, In a field survey on December 14, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 1, Sherman Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838 8" Beech S28°W 25 Links (16.5')#1 8" Beech S83°E 45 Links (29.7')#2 Southwest Corner, Section 36, T14N R13W, West 35 Links (23.10')#6

Robert A. Griffin R.L.S. #13584 LCRC #453 August 6, 1977 Searched for but did not find evidence of this corner. I reestablished this corner on the township line G.L.O. distance (35 Links) East of the recovered Southwest Corner of Section 36, T14N R13W. Set a 5" square X 36" concrete monument with brass cap. 4" X 7" Post South 32.95' #3 7" - 10" Twin Maple S01°E 65.30' #4 4" Jack Pine S45°W 59.63' #5 Concrete monument (Southwest Corner, Section 36, T14N R13W) West 23.10' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 5" square concrete monument with brass cap on North edge of the East and West dirt road and the centerline is 9 feet South. The condition of the recorded witnesses are: #1 and #2 gone, #3 lying down, #4 good condition, #5 gone, #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted the 5" square concrete monument with brass cap as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

16" - 12" Twin Maple S01°W 65.31' Found blaze and found cabin spike in West side of tree. #4 5" square concrete monument (Southwest Corner, Section 36, T14N R13W) West 23.15' #6 6" White Pine (blazed) North 46.57' Set spike with tag #22439 in East side of tree. 14" - 6" Twin Red Pine (blazed) N49°E 61.23' Set spike with tag #22439 in Southeasterly side of tree. 16" White Oak (blazed) S40°E 32.66' Set spike with tag #22439 in Northeasterly side of tree.

Signed by Norman L. Ochs Date December 18, 1998 Surveyor's Michigan License No. 22439

Approved by Peer Review Group on December 22, 1998 Norman L. Ochs, County Representative.

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

