

**SURVEY & REMONUMENTATION**

**1998 Newaygo County Remonumentation Project**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

MAR 02 1999

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'99 FEB 17 PM 3 38

For corners in  
Newaygo SECTION  
(County)

Located in:

Corner Code #

*Linda M. Brown*

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>13N</u> R <u>13W</u> | <u>L-1</u> |
|                                    | T ___ R ___               | _____      |
|                                    | T ___ R ___               | _____      |
|                                    | T ___ R ___               | _____      |
| 2. Property Controlling in Section | S ___ T ___ R ___         | _____      |
|                                    | S ___ T ___ R ___         | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___         | _____      |
|                                    | S ___ T ___ R ___         | _____      |

VOL. 2

222

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Norman L. Ochs, in a field survey on December 14, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

North One Quarter Corner, Section 1, Sherman Township, Newaygo County, Michigan.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Did not set.

Robert A. Griffin R.L.S. #13584  
LCRC #454 August 13, 1977 Searched for but did not find evidence of this corner. I then established this corner equal distance between the Northwest Corner and the Northeast Corner of Section 1 and on the township line. Set a 5" square X 36" concrete monument with brass cap.  
24" White Oak S48°W 17.85' #1  
4" X 7" Post South 32.93' #2  
4" White Oak S07°W 75.41' #3  
6" White Oak S29°W 59.61' #4  
Concrete Monument East 0.62' (South One Quarter Corner, Section 36, T14N R13W)#5

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 5" square concrete monument with brass cap. The centerline of the East and West dirt road is 3 feet ± North. The condition of the recorded witnesses are: #1 thru #5 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Accepted the 5" square concrete monument with brass cap as a substantial marker for the section corner and is accepted as the best available position for the location of this corner.

36" White Oak (blazed) S53°W 17.91' Set spike with tag #22439 above old spike in Southeast side of tree. #1  
4" X 7" Post South 32.93' #2  
10" White Oak (blazed) S13°W 75.66' Found cabin spike in East side of tree. #3  
14" White Oak (blazed) S36°W 59.66' Found cabin spike in West side of tree. #4  
5" square concrete monument (South One Quarter Corner, Section 36, T14N R13W) East 0.62' #5

Signed by \_\_\_\_\_ Date December 18, 1998

Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 22, 1998  
Norman L. Ochs, County Representative.

Revised May 14, 1975  
Revised Jan., 1983