

1993  
1993 NEWAYGO COUNTY REMONUMENTATION PROJECT  
COMMISSION

NEWAYGO COUNTY  
REGISTER OF DEEDS  
MARLENE TOOGOOD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'94 JAN 21 PM 3 25

For corners in

<u>Newaygo</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>14W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Marlene Toogood*

VOL 001 PAGE 18

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman L. Ochs, in a field survey on December 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

W. 1/4 Corner, Section 6, Dayton Twp., Newaygo Co., MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Mullet Brookfield 1837  
9" Beech N48°W 12 lks. (7.92') #1  
16" Beech S73°W 33 lks. (21.78') #2

June 27, 1978  
Newaygo Eng. & Survey Co.  
Found 1 1/2" Rod in Monument Box  
3" Maple N89°W 38.83' #6  
12" Apple Stump S47°W 80.20' #5  
40" Beech East 70.87' #3

Sept. 4, 1935 Highway Dept.  
Found 1 1/2" x 18" Iron Pipe  
30" Beech S88°40'E 69.70' #3  
18" Maple S70°30'E 23.66' #4  
10" Apple S47°W 79.75' #5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1935 the Highway Dept. found 1 1/2" Iron Pipe. They measured N00°52'W 2620.64' from the W. 1/4 Cor. to the Nw. Cor. and measured S01°05'E 2642.29' from the W. 1/4 Cor. to the SW. Cor. of said section. In 1978 Newaygo Eng. & Survey Co. found 1 1/2" rod in Monument box. Centerline of M-82 is 0.40' West of Mon. Box. Mon. Box is on fence row going East. We measured N00°52'27"W 2619.31' from the W. 1/4 Cor. to the NW. Cor. and measured S01°05'00"W 2641.79' from the W. 1/4 Cor. to the SW. Cor. Williams and Works did a section break of Sec. 1, Greenwood Twp., Oceana Co., MI. They measured N01°23'58"W 2620.04' from the E. 1/4 Cor. to the NE. Cor. and measured S01°36'08"E 2642.95' from the E. 1/4 Cor. (Common Cor.) to the SE. Cor. of said section. Found 1/2" rod in monument box. Replaced with 4" Harrison Cast Iron Monument.

Condition of recorded witness is: #1 and #2 Gone #3 Poor Condition #4 Gone #5 Gone #6 Good Condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" Harrison Cast Iron Monument as a Substantial Marker for the 1/4 Corner and is accepted as a careful and faithful re-establishment of the original corner.

48" Beech S89°E 69.70' Spike in the South side of tree #3  
12" Maple N89°W 38.83' #6  
1 1/2" x 1.5' x 3.5' Conc. Pillar with axle shaft in center East 30.35'  
5" S. Maple N33°W 68.12' Spike in SW. side of tree

Signed by Norman L. Ochs  
Surveyor's Michigan License No. \_\_\_\_\_

Date December 27, 1993

Approved by Peer Review Group December 27, 1993  
Norman L. Ochs, County Representative

