

MAY 28 1997

1996 Newaygo County Remonumentation Project

'97 FEB 12 PM 4 45

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in
Newaygo
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 13N R 14W _____ C-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 1 PAGE 246

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Norman L. Ochs, in a field survey on October 3, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 5, Dayton Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838
24" Beech S48°W 32 Links (21.12') #1
10" Beech S73°E 16 Links (10.56') #2
Southeast Corner, Section 31, Denver Township
East 22 Links (14.52') #3

Patrick A. Salisbury R.L.S. #13594
LCRC #341 May 1, 1975
Found Plow Point raised with 1/2" Rod
Southeast Corner, Section 31, Denver Township, East 14.22' #3
8" Catalpa S69°E 110.00' #7
Power Pole N61°E 104.86' #8
24" Pine N48°W 47.69' #5

Ralph A. Smith R.L.S. #3421
Book 55 Page 43 March 3, 1954
Fence Corner N35°W 29.3' #4
6" Pine N45°W 47.1' #5
12" Apple S20°W 64.5' #6
Iron, Stone, and Glass (Southeast Corner, Section 31, Denver Township) East 14.5' #3

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" X 18" Rerod, Plow Point, Crockery and a large stone in centerline of East and West gravel road and in the centerline of the gravel road going South and the centerline of the bituminous road going North is 15 feet East and the condition of the recorded witnesses are: #1 and #2 gone, #3 good condition, #4 gone, #5 good condition, #6 and #7 gone, #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1/2" X 18" Rerod and Plow Point and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

1/2" Rerod (Southwest Corner, Section 31, T14N R14W) East 14.25' #3
34" White Pine N45°W 47.1' Set spike with tag in East side of tree. #5
Power Pole N64°E 104.94' Found spike in Northerly side of pole. #8
18"-14"-14"-12" Quadruplet Elm S22°E 72.59' Set spike with tag in West side of tree.
14" White Pine N09°W 82.90' Set spike with tag in Easterly side of tree.

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996
Norman L. Ochs, County Representative.

M.L.O.

