

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 35

Linda M. Brown

For corners in Newaygo (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 13N R 14W D-5 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2

87

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on August 23, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 8, Dayton Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Mullett 1838
 10" Beech N17°E 18 Links (11.88') #1
 10" Beech S81½°E 23 Links (15.18') #2

Stanley Kass R.L.S. #34972
 LCRC #1181 February 23, 1993
 Established corner at intersection of physical centerline of gravel road and old fence, tree and stone row which extends a half of a mile North in Section 8, bearing toward North One Quarter Corner. Row also extends one quarter of a mile South into Section 17. East and West fences intersecting row in Section 17, support North and South position of established corner.
 Set ½" X 24" Iron Rod capped "Westshore 34972"
 Maple Clump N65°E 66.70' Nail in root. #3
 20" Elm South 19.64' #4
 Basswood Clump North 33.32' #5
 8" Elm N56°W 27.24' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found ½" X 24" Rod and Cap #34972 on fence line and woods line going North. The centerline of the gravel road going East and West is 1 foot South and the condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed ½" Rod and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Clump Maple N72°E 66.70' Found spike in root West side of tree. #3
 20" Elm South 19.70' Set spike and shinner West side of tree. #4
 Basswood N06°E 33.27' Found spike West side of tree. #5
 10" Elm N48°W 26.79' Found spike North side of tree. #6

Signed by Norman L. Ochs Date September 8, 1997
 Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on October 14, 1997
 Norman L. Ochs, County Representative.

Revised May 14, 1975
 Revised Jan., 1983

N.L.O.

