

SURVEY & REMONUMENTATION

MAR 02 1999

1998 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'99 FEB 17 PM 3 38

*Linda M. Brown*

SECTION

For corners in  
Newaygo  
(County)

Located in:

Corner Code #

1. Public Land Survey

T 13N R 14W

D-13

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Norman L. Ochs, in a field survey on June 29, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

South One Quarter Corner, Section 32, Dayton Township, Newaygo County, Michigan.

Register of Deeds Stamp & File Number

VOL. 2

209

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1837  
9" Elm N01°W 25 Links (16.5')#1  
12" Elm N57°E 32 Links (21.12')#2

No other previous history.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found no evidence of monument. Established position of corner per Ralph A. Smith, June 24, 1965 survey (Book 84 Pages 80 and 81). Based on Ralph A. Smith's distance from the North One Quarter Corner, Section 5, T12N R14W, and on line with the Southeast corner, Section 32, and the North One Quarter corner, Section 5, T12N R14W. The centerline of the East and West bituminous road is 2 feet ± South. The condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

6" Hickory (blazed) N47°E 50.20' Set spike with tag #22439 in West side of tree.  
8" Ash (blazed) N18°W 43.12' Set spike with tag #22439 in East side of tree.  
18" Ash S22°E 74.07' Set spike with tag #22439 in Easterly side of tree.  
Power Pole S53°W 69.10' Set spike with tag #22439 in Northerly side of pole.  
North One Quarter Corner, Section 5, T12N R14W (2 3/4" X 20" Harrison cast iron monument in monument box) East 24.14'

Signed by *Norman L. Ochs* Date October 15, 1998  
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on October 22, 1998  
Norman L. Ochs, County Representative.

*N.L.O.*

