

**SURVEY & REMONUMENTATION**

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

MAR 02 1999

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'99 FEB 17 PM 3 38

*Linda M. Brown*

For corners in SECTION Newaygo (County)

Located in: Corner Code #

- 1. Public Land Survey T 13N R 14W F-13
- T \_\_\_ R \_\_\_
- T \_\_\_ R \_\_\_
- T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_
- in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_
- Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

VOL. 2

213

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on May 13, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

South One Quarter Corner, Section 33, Dayton Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Mullett and Brookfield 1837  
6" Beech N48°W 22 Links (14.52') #1  
6" Sugar N47°E 11 Links (7.26') #2

James E. Evans R.L.S. #22431  
November 11, 1981 Drawing Number 81117B  
Found ¾" Pipe in Monument Box  
8" Locust N40°W 43.60' #3  
30" Elm South 27.60' #4  
North One Quarter Corner, Section 4, T12N R14W, East 16.57' #5

William Fries, Jr. R.L.S. #30389  
LCRC #1028 August 6, 1990  
Found empty Monument Box  
Iron and Cap #30389 North 50.00' #7  
Power Pole S72°E 142.93' #7  
Power Pole S12°E 44.46' #8  
3" Pipe S01°W 52.71' #9

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 1½" X 16" Iron Pipe in monument box and the centerline of the East and West bituminous road is 2 feet North and the chain-link fence going North is 3 feet East. The condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #9 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed Iron Pipe and monument box and set a 2¾" X 20" Harrison cast iron monument marked "County Survey" in a new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- North One Quarter Corner, Section 4, T12N R14W (2¾" X 20" Harrison cast iron monument in monument box) East 16.65' #5
- ½" Rerod with cap #30389 North 50.05' #6
- Power Pole S70°E 142.90' Found spike in Northeasterly side of pole. #7
- Power Pole S05°E 44.50' Found P.K. nail with tag "Advanced Survey & Map" in West side of pole. #8
- 3" diameter Pipe (8 feet tall) S05°E 52.50' #9
- Power Pole N35°W 53.80' Found P.K. nail with tag #22439 in Easterly side of pole.
- 14" Elm N45°W 91.28' Found spike in Easterly side of tree.
- 16" Locust North 103.60' Found spike in West side of tree.

Signed by Norman L. Ochs  
Norman L. Ochs

Date October 15, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors

Approved by Peer Review Group on October 22, 1998  
Norman L. Ochs, County Representative.

*N.L.O.*

