

**SURVEY &
REMONUMENTATION**

1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

VOL **001** PAGE **116**

For corners in

<u>Newaygo</u> <small>(County)</small>	Located In:	Corner Code ≠
1. Public Land Survey	T <u>13N</u> R <u>14W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 56

Marlene Toogood
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Norman L. Ochs, in a field survey on May 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.
SW Corner, Sec. 12, Dayton Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Mullett 1838 10" Hemlock N11°E 13 lks. (3.58') #1 15" Hemlock S57°E 28 lks. #2	N.C.R.C. Sheet Iron and Plow Landside SW. Cor. House N47°E 113.60' #3 P. Pole N68°E 60.0' #4 P. Pole S18°E 79.9' #5	Patrick A. Salisbury R.L.S. #13594 Jan. 28, 1972 Found 5/8" Rod SW. Cor. House N50°E 113.75' #3 P. Pole N70°E 60.43' #4 P. Pole S18°E 80.10' #5 Series E, No. 9051
J.C. Brewster (Co. Surveyor) Book A Page 121 November 10, 1892 Pine Root Stake Measured 39.60 1/2 chains (2613.93') from the SW. Cor. to the W. 1/4 Cor of Sec. 12.	Patrick A. Salisbury Jan. 28, 1972 measured 2673.10 feet from the SE. Cor. to the S. 1/4 Cor. of Sec. 11. Measured 2632.45 feet from the SW. Cor. to the S. 1/4 Cor. Sec. 12. See reversed side for more info.-->	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On May 18, 1994, I, Norman L. Ochs, found a 1 1/4" Gas Pipe 12" long in Monument Box at road intersection of 16th Street and Warner Avenue and replaced with a 4" dia. Harrison Cast Iron Monument 20" long stamped County Surveyor in the exact location. I measured 2617.68 feet from the SW. Corner to the W. 1/4 Corner of Section 12 and condition of recorded witnesses are: #1 Thru #4 Gone, #5 Good Condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" dia. Harrison Cast Iron Monument 20" long stamp County Surveyor as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.
P. Pole S85°E 100.46' Spike in NE. side of pole
P. Pole S18°E 80.10' Spike in NE. side of Pole #5
6" Apple S32°W 104.60' Spike in SE. side of tree
M.B.T. Junction Box N43°W 52.55' (Top and center) #5795



Signed by Norman L. Ochs Date November 14, 1994

Surveyor's Michigan License No. 22439
Accepted by Peer Review Group on November 10,
Norman L. Ochs, County Representative. *N.L.O.*

A: Description.....(Continued)

Patrick A. Salisbury R.L.S. #13594 Jan. 28, 1972

Measured 2639.20 feet from the NW. Corner to the W. 1/4 Corner of Sec. 13 and measured 2618.86 feet from the W. 1/4 Corner to the SW. Corner of Sec. 12.