

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 JAN 21 PM 3 27

For corners in

NEWAYGO

(County)

Located In:

Corner Code #

1. Public Land Survey

T 14N R 13W

A-2

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Marlene Toogood*

VOL 001 PAGE 38

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on December 4, 19 93,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

W-1/4 Corner, Sec. 6, Lincoln Twp.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Milton Nye 1856 6-30-61 George Blass #5489 NCRC Sheet  
6" Birch N65°W 28 lks #1 Set 6" dia. 5' lg. conc. mon. 10" Maple S38°W 128.50'  
7" Hemlock S44°W 36 lks #2 10" Maple S38°W 128.50 #3 10" W. Oak N57°W 160.17' #4.  
10" W. Oak N57°W 160.17 #4 7" Norway Pine N85°E 220.60' #5.  
7" Norway Pine N85°E 220.60' #5  
LCRC #272

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1961 George Blass located corner site from aerial photograph and original Government notes. Found remains of square Pine stake at intersection of old road grades East, West and South. Roads abandoned. No trace of original Government witnesses were found. He set 6" reinforced conc. mon. at the recovered corner point. The mon. is capped with brass tablet. On Dec. 4, 1993 N. L. Ochs found Blass's conc. mon. in good condition. Found no previous witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Blass's reinforced conc. mon with brass tablet as a substantial marker for the 1/4 corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

13" W. Oak N38°E 120.72' Nail in North side of tree.  
8" Maple S23°E 8.03' Nail in South side of tree,  
18" Maple S64°W 27.29' Nail in Southeast side of tree.  
12" Cherry S69°W 43.51' Nail in SW side of tree.

Signed by

*Norman L. Ochs*

Date December 20, 1993

Surveyor's Michigan License No.

22439

Approved by Peer Review Group December 27, 1993

Norman L. Ochs, County Representative

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

