

**SURVEY &
REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'98 MAR 6 PM 12 36

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>13W</u> T <u>14N</u> R <u>14W</u> T ___ R ___ T ___ R ___	<u>A-3</u> ✓ <u>M-3</u> _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

VOL. 2

101

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on November 6, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 7, Lincoln Township, Newaygo County, Michigan.
Northeast Corner, Section 12, Denver Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838 Resurvey
12" Hemlock N26°E 27 Links (17.82')#1
28" Maple S38°_ 54 Links (35.64')#2

Sammy S. Barnett R.L.S. #16923
Recorded in Liber 348 Pages 4077-4080
September 19, 1988
Found 6" round concrete monument
12" Elm N05°E 25.85' #3
14" White Pine S63°E 22.40' #4
20" Maple S13°W 67.70' #5
14" White Pine S87°W 33.15' #6

George M. Blass R.L.S. #5489
LCRC #273 June 21, 1961
Located corner site from aerial photograph and government notes
Found remains of wood stake along side of corner fence post, fences East and South. Position of stake checks remains of government Hemlock witness tree Northwest. I placed a 6" diameter by 5 foot long reinforced concrete monument 18" above the ground at recovered corner point.
12" Elm N05°E 25.85 (scribed B.T. 6)#3
14" White Pine S63°E 22.40' (scribed B.T. 7)#4
20" Maple S13°W 67.70' (scribed B.T. 12)#5
14" White Pine S87°W 33.15' (scribed B.T. 12)#6

OVER ↵

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found George Blass 6" diameter concrete monument with brass cap, 10 inches above ground, on line with remains of fence running South and East. The woods line going South is 200 feet East. The corner is on extension of woods line going East. The condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:


Accepted 6" diameter concrete monument with brass cap as a substantial marker for the section corner and is accepted as a perpetuation of the original corner.

26" White Pine (blazed) S55°E 22.4' Set spike and washer in Northerly side of tree. #4
24" Maple (blazed) S18°W 67.7' Set spike and washer in Westerly side of tree. #5
22" White Pine (blazed) S88°W 33.15' Set spike and washer in North side of tree. #6
20" White Pine (blazed) N12°W 25.58' Set spike and washer in East side of tree.

Signed by *Norman L. Ochs* Date November 10, 1997
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1997
Revised May 4, 1995
Revised Jan 1983



Approved by Peer Review Group on November 11, 1997
Norman L. Ochs, County Representative.

N.L.O.