

**SURVEY & REMONUMENTATION**

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

**LAND CORNER RECORDATION CERTIFICATE**  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'99 FEB 17 PM 3 39

**SECTION**

For corners in Newaygo (County) Located in: T 14N R 13W Corner Code # A-7 ✓  
(County) T 14N R 14W M-7  
 1. Public Land Survey T R  
T R  
T R  
 2. Property Controlling in Section S T R  
S T R  
 3. Miscellaneous Property in Sec. S T R  
S T R  
 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

*Linda M. Brown*

VOL. 2

240

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on December 1, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 18, Lincoln Township, Newaygo County, Michigan.

Southeast Corner, Section 13, Denver Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Mullett and Brookfield 1838 Resurvey Newaygo County Road Commission Sheet  
 10" Hemlock S55°W 35 Links (23.1') #1 1/2" Iron  
 12" Hemlock N65°W 44 Links (29.04') #2 24" Elm N17°E 78.45' #3  
 Power Pole S88°E 94.75' #4

Delos G. Anderson (County Surveyor)  
 June 17, 1897 Book A, Page 205  
 March 26, 27, 28, 1902 Book A, Pages 341 and 342  
 Stone Corner.

OVER ↘

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 1/2" Rerod (driven thru cap) presumed used to raise 6" diameter Concrete Monument with brass plate. The centerline of the North and South bituminous road is 5 feet ± West and there is no apparent East and West occupation. The condition of the recorded witnesses are: #1 thru #3 gone, #4 and #5 good condition, #6 gone, #7 thru #9 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Accepted 1/2" Rerod over the 6" diameter Concrete Monument with brass plate as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole S85°E 95.04' Found spike in North side of pole. #4  
 36" White Oak S80°E 153.60' Found nail with tag (Advanced Survey & Map) in South side of base of tree. #7  
 14" Cherry (blazed) S16°E 53.43' Found spike in Westerly side of tree. #7  
 1/2" Rerod with cap #30389 West 33.04' #8  
 30" White Oak (blazed) N15°E 133.90' Found spike with tag (Advance Survey & Map) in West side of tree. #9  
 Cut "X" in Large Stone (36" diameter, 18" above grade) S85°W 30.66'

Signed by Norman L. Ochs Date December 4, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Approved by Peer Review Group on December 8, 1998

Norman L. Ochs, County Representative.

*N.L.O.*



A. Description (cont.)

George Blass R.L.S. #5489

June 23, 1961 LCRC #277

Located corner site from aerial photograph and government notes. Found 1/2" X 15" reinforcing Rod in gravel road North and South, Power line West, corner was 4 feet East of the centerline of the North and South road. From the witnesses of the Newaygo County Road Commission I placed a 6" diameter by 5 feet long reinforced Concrete Monument 1 foot below the surface of the road, at the recovered corner point. The monument is capped by a 3 1/2" diameter brass tablet.

30" Elm (scribed B.T. 18) N15°E 78.55' #3

16" White Oak (scribed B.T. 19) S83°E 153.10' #5

14" Twin Elm (scribed B.T. 19) S16°E 80.43' #6

Norman L. Ochs R.L.S. #22439

January 8, 1975 Found Concrete Monument

Power Pole S88°E 95.11' #4

10" Cherry S20°E 53.48' #7

24" Elm Stump N17°E 78.45' #3

William Fries, Jr. R.L.S. #30389

September 1995 1/2" Iron and cap

24" White Oak N09°E 133.90' #9

Power Pole East 94.98' 34

29" White Oak S85°E 153.26' #5

1/2" Iron and cap #30389 N89°W 33.00' #8

Norman L. Ochs R.L.S. #22439

August 8, 1996 Drawing Number 96210B

Found 1/2" Rod and cap #30389

Power Pole S88°E 95.11' #4

10" Twin Cherry S20°E 53.48' #7

1/2" Rod and cap #30389 West 33.00' #8

28" White Oak N20°E 134.00' #10

SURVEY &  
RECONSTRUCTION

MAR 02 1999

SECTION