

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'99 FEB 17 PM 3 39

Linda M. Brown

VOL. 2

241

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 14N R 13W T 14N R 14W T ___ R ___ T ___ R ___	<u>A-8</u> ✓ <u>M-8</u> _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on February 6, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 19, Lincoln Township, Newaygo County, Michigan.

East One Quarter Corner, Section 24, Denver Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838
7" Beech S48°W 23 Links (15.18') #1
8" Beech N33°W 40 Links (26.4') #2

Newaygo County Road Commission Sheet
1/2" Iron
Power Pole N22°E 117.2' #3
Fence Post S86°E 24.7' #4

Norman L. Ochs R.L.S. #22439
Drawing Number 92415B
Power Pole N22°E 117.65' #3
Fence Post S88°E 24.47' #4
Fence Post S88°W 33.82' #8
14" - 14" Twin Cherry S20°E 112.34' #7

George Blass R.L.S. #5489
LCRC #278 June 23, 1961
Found 5/8" Iron reinforcing Rod in gravel road North and South in line with very old fences East and West 3 feet East of centerline of road North and South from witnesses of Newaygo County Road Commission.
Set 6" diameter by 5 foot long reinforced Concrete Monument
16" White Oak N05°E 186.00' #5
22" Twin Red Oak N88°E 236.15' #6
8" Triple White Cherry S10°E 110.86' #7

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" diameter X 8" Rod over 3" diameter brass cap in 6" concrete cylinder and the centerline of the North and South road is 3.5 feet West. The fence line going East is 3 feet South and on field line going West. The condition of the recorded witnesses are: #1 and #2 gone, #3 and #4 good condition, #5 stump, #6 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rod and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" over concrete cylinder as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.


Power Pole N26°E 117.55' Found spike in West side of pole. #3
Fence Post S82°E 24.54' Found spike in South side of post. #4
16" Stump N11°E 186.3' to center. #5
22" - 38" Twin Red Oak S88°E 237.68' Set spike with tag #22439 in South side of tree. #6
16" - 21" White Cherry S05°E 112.28' Middle of both trees found spike in West side of tree. #7
Fence Post S88°W 33.92' Found spike in south side of post. #8

Signed by Norman L. Ochs Date November 5, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors

Approved by Peer Review Group on November 10, 1998
Norman L. Ochs, County Representative.



Revised May 14, 1975
Revised Jan., 1983

N.L.O.