

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 14N R 13W E-4 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

VOL. 2 PAGE 10

Register of Deeds Stamp & File Number

Grid with columns A-M and rows 2-13. A dot is present at row 4, column E.

I, Norman L. Ochs, in a field survey on December 9, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 9, Lincoln Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856 14" White Pine N26°E 49. Links (32.34') #1 8" Beech S25°W 24 Links (15.84') #2

William M. Jacques (County Surveyor) Book B Page's 14 and 15 December 9, 1904 Set stake with broken glass around Measured 29.64 Chains (2617.49') from the West One Quarter Corner to the Center One Quarter Corner of Section 8 and measured 43.53 Chains (2872.98') from the Center One Quarter Corner to the East One Quarter Corner of Section 8 and measured 40.88 Chains (2698.08') from the Southwest Corner to the West One Quarter Corner of Section 9 and measured 40.88 Chains (2698.08') from the West One Quarter Corner to the Northwest Corner of Section 9.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found nothing, this area is in a ± 2 feet cut in roadway. Set corner by pushing line from the West One Quarter Corner thru the Center Quarter Corner fences of Section 8 with grade split along the West line of Section 9 and measured 5163.62 feet from the West One Quarter Corner to the East One Quarter Corner of Section 9 and measured 2684.34 feet from the Southwest Corner to the West One Quarter Corner of Section 9 and in the centerline of the North and South gravel road and the North and South Right-of-Way fence is 32.5 feet West and measured 2617.49 feet from the West One Quarter Corner to the Center One Quarter Corner of Section 8 and measured 2875.98 feet from the Center Quarter Corner to the East One Quarter Corner of Section 8 and the condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole S39°E 36.73' Set spike and tag in Northeast side of pole. 24" White Oak N61°E 50.24' Set spike and tag in North side of tree. 40" White Oak S30°W 78.19' Set spike and tag in North side of tree. 10" White Pine East 47.71' Set spike and tag in North side of tree.

Signed by Norman L. Ochs Date December 11, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group On December 23, 1996 Norman L. Ochs, County Representative.

N. L. O.

