

**SURVEY & REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS  
LINDA M. BROWN

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'98 MAR 6 PM 12 36

*Linda M. Brown*

For corners in Newaygo (County) Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 14N R 13W E-8  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

VOL. 2

107

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on November 11, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

West One Quarter Corner, Section 21, Lincoln Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Milton Nye Resurvey 1856  
 6" Hemlock Corner Tree  
 4" Hemlock N18°W 11 Links (7.26')#1  
 10" Beech S75°E 19 Links (12.54')#2

William M. Jacques (County Surveyor)  
 Book 23 Page 3 May 15, 1907  
 Iron Corner

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 2 1/4" at top and 1 1/4" at bottom by 9" long Iron Rod with broken glass. On line with remnants of East and West fence and on line with remnants of fence going South. Found remnants of a fence going North 36 feet East. The condition of the recorded witnesses are: #1 and #2 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed Iron and set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" over glass in hole as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

10" Red Pine (blazed) S08°E 13.17' Set spike and brass washer #22439 in West side of tree.  
 12" Red Pine (blazed) S45°E 24.81' Set spike and brass washer #22439 in East side of tree.  
 14"-14"-16" Triple Maple (blazed) N13°W 13.08' Set spike and brass washer #22439 in East side of tree.  
 6" White Oak (blazed) N70°E 38.11' Set spike and brass washer #22439 in South side of tree.

Signed by Norman L. Ochs Date December 15, 1997

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 18, 1997 Revised May 14, 1975  
 Norman L. Ochs, County Representative. Revised Jan., 1983

*M.L.O.*

