

**SURVEY & REMONUMENTATION**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

MAR 19 1998

1997 Newaygo County Remonumentation Project

'98 MAR 6 PM 12 36

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

*Linda M. Brown*

**SECTION**

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>13W</u>	<u>E-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

108

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on November 1, 19 97, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southwest Corner, Section 21, Lincoln Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Milton Nye Resurvey 1856 8" Beech N65°W 15 Links (9.9') #1 7" Beech S65°E 13 Links (8.58') #2	Ralph A. Smith, R.L.S. #3421 Witness Book Number 1 Page 36 1" Gas Pipe October 25, 1956 Forestry Post N10°W 31.3' #3 10" Beech S50°E 10.3' #4
Delos G. Anderson (County Surveyor) Book A Pages 179 and 180 October 12, 1895 Original Corner	

Newaygo Engineering and Survey Company  
LCRC #591 December 22, 1978  
Found a 1" Pipe. Centerline of trail road going East is 18 feet South of corner.  
16" Beech S48°E 10.66' #4  
10" Red Oak N10°E 2.82' #5  
18" Forked Beech N65°E 20.35' #6

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 1" X 22 1/2" Pipe and three stones (5" in diameter) piled around it. In the centerline of old North and South road. The centerline of the old trail road going East and West is 17 feet South. The condition of the recorded witnesses are: #1 and #2 gone, #3 leaning, #4 good condition, #5 stump, #6 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed 1" Pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" with stones piled around, as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Forestry Post (leaning) N15°W 31.3' to center of post. #3  
30" Beech S50°E 10.63' Found spike in North side of tree. #4  
Oak Stump N07°E 2.82' Found spike in Southeast side of tree. #5  
30" Forked Beech N60°E 20.35' Set spike and brass washer in Southeast side of tree. #6  
10" White Oak S69°W 63.50' Set spike and brass washer in North side of tree.  
8" Maple N56°W 49.91' Set spike and brass washer in North side of tree.

Signed by *Norman L. Ochs* Date November 10, 1997  
Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on November 11, 1997  
Norman L. Ochs, County Representative.



*N.L.O.*

Revised May 14, 1975  
Revised Jan., 1983