

1996 Newaygo County Remonumentation Project

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

COMMISSIONER

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 14N R 13W G-3 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

VOL. 2 PAGE 11

Register of Deeds Stamp & File Number

Table with columns A-M and rows 2-13. A dot is present in row 3, column G.

I, Norman L. Ochs, in a field survey on November 25, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northeast Corner, Section 9, Lincoln Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856 12" Tamarack N36°W 33 Links (21.78')#1 11" Tamarack S50°E 34 Links (22.44')#2

Newaygo Engineering and Survey Company January 25, 1985 Found 8" Cedar Post in swamp with notches of North and West sides in line with old woods line North and South and fits G.L.O swamp calls 5" Red Maple N57°E 20.40' #3 24" White Pine N12°E 13.54' #4 12" White Pine S41°W 31.35' #5

Lyle S. Shepherd R.L.S. #503 Book 40 Page's 16-22 October 14, 1918 Stake

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found Cabin Spike in top of broken wood post in swamp and measured 2627.87 feet from the Northeast Corner to the East One Quarter Corner of Section 9 and measured 2603.92 feet from the Northeast Corner to the North One Quarter Corner of Section 10 and the condition of the recorded witnesses are: #1 and #2 gone, #3 thru #5 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set 3/4" X 5' Pipe over top of spike in post (Pipe is ± 1 foot above ground) in swamp as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

6" Red Maple N60°E 19.9' Found spike in Northwest side of tree. #3 25" White Pine N22°E 13.41' Found spike in Southeast side of tree. #4 14" White Pine S48°W 31.75' Set spike and tag in Northwest side of tree. #5 3" Maple S65°E 9.85' Set spike and tag in Southwest side of tree.

Signed by Norman L. Ochs Date November 30, 1996 Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group On December 11, 1996 Norman L. Ochs, County Representative.

N. L. O.

