

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 14N R 13W G-4 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

Linda M. Brown

VOL. 2 PAGE 12

Register of Deeds Stamp & File Number

Table with columns A-M and rows 2-13. A grid for recording deed stamps and file numbers.

I, Norman L. Ochs, in a field survey on November 22, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 10, Lincoln Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856 18" White Pine S50°W 11 Links (7.26')#1 8" Beech S50°E 19 Links (12.54')#2 Measured 80.25 Chains (5296.50') from the Northwest Corner to the Southwest Corner of Section 10 and measured 39.50 Chains (2607.0') from the Northwest Corner to the West One Quarter Corner of Section 10 and measured 40.75 Chains (2688.73') from the West One Quarter Corner to the Southwest Corner of Section 10.

William M. Jacques (County Surveyor) Book 8 Page's 61 and 62 January 31, 1906 20" Pine Stump N21°W 35 1/4 Links (23.60')#3 Measured 78 Chains (5148 feet) from the East One Quarter Corner to the West One Quarter Corner of Section 9

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found fence intersection, North, South, East and West (had to dig to find) and set monument at intersection of fences and measured 2688.73 feet from the Southwest Corner to the West One Quarter Corner of Section 10 and measured 2627.87 feet from the West One Quarter Corner to the Northwest Corner of Section 10 and measured 5316.6 feet from the Northwest Corner to the Southwest Corner of Section 10 and the condition of the recorded witnesses are: #1 thru #3 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set 4" diameter Harrison cast iron monument 30" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

24"-8" Twin Beech N22°W 10.38' Set spike and tag in West side of tree. 28" White Oak S35°E 28.00' Set spike and tag in Northeast side of tree. 24" White Oak S38°W 40.48' Set spike and tag in Northwest side of tree. 18" Red Oak East 50'31' Set spike and tag in North side of tree.

Signed by Norman L. Ochs Date November 30, 1996

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group On December 11, 1996 Norman L. Ochs, County Representative.

Revised May 14, 1975 Revised Jan., 1983

N. L. O.

