

SURVEY &  
REMONUMENTATION

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'97 FEB 12 PM 4 4

*Linda M. Brown*

For corners in  
Newaygo  
(County)

Located In: Corner Code #

1. Public Land Survey T 14N R 13W G-5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

VOL. 2 PAGE 13

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0		5		1		3		2				
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on November 21, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 10, Lincoln Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856  
8" Maple N42°E 20 Links (13.2)#1  
18" White Oak S67½°W 17 Links (11.22)#2

Newaygo Engineering and Survey Company  
Found Fence Post and old fences on ground running North and West  
April 20, 1979 Dug around tree - Found nothing

William M. Jacques (County Surveyor)  
Book 8 Page's 61 and 62 January 31, 1906  
Measured 40.06 Chains (2643.96') from the South One Quarter Corner to the Southeast Corner of Section 9 and measured 39 Chains (2574') from the Southwest Corner to the South One Quarter Corner of Section 10

Patrick R. Leemon R.L.S. #31595  
1983 Section Break, Section 15  
Measured 2586.40 feet from the Northwest Corner to the North One Quarter of Section 15 and measured 2878.14 feet from the Northwest Corner to the West One Quarter Corner of Section 15 to fence corners.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found nothing. Set Harrison monument at intersection of fence line going North and fence line going West and measured 2688.73 feet from the Southwest Corner to the West One Quarter Corner of Section 10 and measured 2609.30 feet from the Southwest Corner to the South One Quarter Corner of Section 10 and measured 2868.94 feet from the Southwest Corner of Section 10 to the East One Quarter Corner of Section 16 and the condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 12" White Oak N45°E 12.13' Set spike and tag in Northwest side of tree.
- 8" White Oak S30°E 31.16' Set spike and tag in East side of tree.
- 12"-16"-15" Triple Maple S37°W 19.01' Set spike and tag in East side of tree.
- 24" Black Oak N36°W 35.73' Set spike and tag in Southwest side of tree.

Signed by Norman L. Ochs Date November 30, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group On December 11, 1996  
Norman L. Ochs, County Representative.

*N. L. O.*

