

SURVEY & REMONUMENT

MAY 28 1997

COMMISSIONER

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE '97 FEB 12 PM 4 45 FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

VOL. 2 PAGE 14

Form with fields: For corners in Newaygo (County), Located in: T 14N R 13W, Corner Code # G-6, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

Register of Deeds Stamp & File Number table with columns A-M and rows 2-13. A dot is present in row 6, column F.

I, Norman L. Ochs, in a field survey on November 20, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

East One Quarter Corner, Section 16, Lincoln Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856 5" Beech N70°W 28 Links (18.48')#1 4" Beech S61°E 20 Links (13.20')#2 Measured 85.66 Chains (5653.56') from the Northeast Corner to the Southeast Corner of Section 16 and measured 42.83 Chains (2826.78') from the Northeast Corner to the East One Quarter Corner and measured 42.83 Chains (2826.78') from the East One Quarter Corner to the Southeast Corner of Section 16.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found nothing here. Found stumps 500 feet ± North, could be line trees. Set 4" X 20" Harrison monument on intersection of fence line and on line between Northeast and Southeast corners of Section 16. Corner is on slope of hill 75 feet ± East of crest on hill and on woods line going West and scattered remains of fence line going West (very old - had to dig to find) and measured 5699.09 feet from the Northeast Corner to the Southeast Corner of Section 16 and measured 2868.94 feet from the Northeast Corner to the East One Quarter Corner and measured 2830.15 feet from the East One Quarter Corner to the Southeast Corner of Section 16 and the condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 15" White Oak N20°W 15.66' Set spike in East side of tree. 18" White Oak N42°E 10.43' Set spike in Southeast side of tree. 6" Maple S50°E 17.01' Set spike in Southwest side of tree. 15" Red Oak S65°W 16.17' Set spike in Southeast side of tree.

Signed by Norman L. Ochs Date November 30, 1996 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group On December 11, 1996 Norman L. Ochs, County Representative.

M. L. O.

