

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'99 FEB 17 PM 3 40

For corners in
Newaygo
(County)

Located in: Corner Code #

1. Public Land Survey T 14N R 13W G-7
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

247

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 1, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 15, Lincoln Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye 1856 Resurvey
8" Maple N41°W 44 Links (29.04') #1
5" Maple S45°E 15 Links (9.9') #2

William M. Jacques (County Surveyor)
May 23, 1904 Book 10, Page 57
Glass buried around stake
28" Pine Stump S28½°E 64 Links (42.24') #3
26" Pine Stump N65½°E 61 Links (40.26') #4

B.G. Mikal (U.S.F.S.) 1936
Found Iron Bed Rail
20" Aspen S40°W 27.2' 35
15" White Oak N45°E 56.4' #6
10" White Oak S75°E 101.8' #7

Newaygo County Road Commission Sheet
Iron Bed Rail 1956
12" White Oak N32°E 49.3' #8
18" White Oak N51°E 56.2' #6
16" Elm N50°W 58.9' #9

OVER ↙

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 5" X 5" concrete monument on line ± with the centerline of the gravel road going North and the centerline of the East and West bituminous road is 2 feet ± North and the centerline of the dirt road going South is 8 feet ± East. The condition of the recorded witnesses are: #1 thru #7 gone, #8 good condition, #9 stump, #10 and #11 good condition, #12 did not verify.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 5" X 5" Concrete Monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

20" White Oak (blazed)(with B.T. tag) N37°E 49.85' Found dock spike in Southeasterly side of tree. #8
24" Stump (mostly decayed) N45°W 89.0' ± to center. #9
16" Maple (blazed)(with B.T. tag) N60°E 99.80' Found dock spike in Westerly side of tree. #10
14" Black Oak (blazed)(with B.T. tag) S20°E 84.00' Found dock spike in West side of tree. #11
18" Red Oak (blazed) S40°W 45.26' Set spike with tag #22439 in Northwesterly side of tree.

Signed by Norman L. Ochs Date December 4, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 8, 1998
Norman L. Ochs, County Representative.

Revised May 14, 1975
Revised Jan., 1983



N.L.O.

A. Description (cont.)

Robert A. Griffin R.L.S. #13584

July 13, 1983 LCRC #575 and Field Notes

Found a wood stake, raised with Bed Rail 38" long, raised with a 3/4" X 26" Iron Rod, raised with a 1 1/4" X 9" Iron Pipe with stones and broken glass throughout from witnesses removed and set a 5" X 36" Concrete monument with brass cap.

15" White Oak N45°E 56.4' #6

10" White oak S75°E 101.8' #7

South Maple N58°E 99.95' #10

16" White Oak N33°E 50.03' #8

8" Black Oak S21°E 84.32' #11

South One Quarter Corner, Section 15, N89°12'09"E 2619.84' #12

Norman L. Ochs R.L.S. #22439

January 18, 1985 Found Robert A. Griffin big spike.

14" White Oak N33°E 49.88' #8

12" Maple N58°E 99.92' #10

10" Maple S21°E 84.05' #11

18" White Oak N51°E 56.2' #6

16" Elm Stump N50°W 88.9' #9

SURVEY &
REMONUMENTATION

MAR 02 1989

SECTION