

SURVEY &  
REMONUMENT

MAY 28 1997

COMM

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'97 FEB 12 PM 4 45

For corners in  
Newaygo  
(County)

Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 14N R 13W H-5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Linda M. Brown*

VOL. 2 PAGE 16

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	29	28	27	26	25								
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on November 25, 19 96, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 10, Lincoln Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856  
10" Beech N63°E 26 Links (17.16') #1  
14" White Pine S56°W 30 Links (19.80') #2

Lyle S. Shepherd R.L.S. #503  
Witness Book Number 1 Page 39  
10" Pine Stump N25½°E 38.0' #3  
12" Pine Stump S33½°E 32.25' #4

Patrick R. Leemon R.L.S. #31595  
Measured 2586.40 feet from the Northwest Corner to the North One Quarter Corner of Section 15 and measured 2542.12 feet from the North One Quarter Corner to the Northeast Corner of Section 15

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found nothing. Set Harrison monument on fence lines going North and East and in West edge of two-track going Northeast and Southwest and 25± feet Southwest of gate and measured 2609.30 feet from the Southwest Corner to the South One Quarter Corner of Section 10 and measured 2536.49 feet from the South One Quarter Corner to the Southeast Corner of Section 10 and the condition of the recorded witnesses are: #1 thru #4 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 30" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

18" Black Oak N53°W 3.29' Set spike and tag in Southwest side of tree.  
18" Black Oak S70°E 15.23' Set spike and tag in Northeast side of tree.  
5" White Oak S25°E 37.95' Set spike and tag in Northeast side of tree.  
10" White Oak S63°W 26.5' Set spike and tag in Northwest side of tree.

Signed by Norman L. Ochs Date November 30, 1996

Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975

Approved by Peer Review Group On December 11, 1996

Revised Jan., 1983

Norman L. Ochs, County Representative.

*N. L. O.*

