

SURVEY & REMONUMENTATION

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUN
REGISTER OF DEEDS
LINDA M. BROW

'99 FEB 17 PM 2:44

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

SECTION

Linda M. Brow

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>13W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

250

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on December 1, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 15, Lincoln Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye 1856 Resurvey
6" White Oak N32½°W 34 Links (22.44') #1
7" White Oak S20°E 20 Links (13.2') #2

Robert A. Griffin R.L.S. #13584
LCRC #575 and 576 1983 - Field Notes
Found ½" Iron from Newaygo County Road Commission
Witnesses. Set a 5" X 36" Concrete Monument with brass cap.
10" Black Oak S14°W 97.03' #6
6" Red Pine N29°E 55.53' #8
Fiberglass Post South 32.99' #9
8" White Oak N30°W 41.2' #3
8" White Oak N09°W 31.1' #4
8" Black Oak S66°W 77.9' #5

Newaygo County Road Commission Sheet
½" Iron
8" White Oak N30°W 41.2' #3
8" White Oak N09°W 31.1' #4
8" Black Oak S66°W 77.9' #5

OVER ↙

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 5" X 36" concrete monument. The centerline of the East and West bituminous road is 1 foot ± South. There is no apparent North and South occupation. The condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #9 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 5" X 36" Concrete Monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

20" Black Oak (blazed) S69°W 78.53' Set spike with tag #22439 in Northwesterly side of tree. #5
14" Black Oak (blazed)(with B.T. tag) S09°W 97.09' Found dock spike in East side of tree. #6
6" White Oak (blazed)(with B.T. tag) N35°W 61.32' Found dock spike in Southwesterly side of tree. #7
8" Red Pine (blazed)(with B.T. tag) N34°E 55.52' Found dock spike in Northwesterly side of tree. #8
Carsonite Post South 33.0' ± to center. #9

Signed by Norman L. Ochs Date December 4, 1998
Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 8, 1998
Norman L. Ochs, County Representative.

Revised May 14, 1975
Revised Jan., 1983



N.L.O.

A. Description (cont.)

Norman L. Ochs R.L.S. #22439

January 22, 1985 Found big spike set by Robert A. Griffin.

6" Red Pine N29°E 55.53' #8

4" White Pine N38°W 61.32' #7

10" Red Oak S14°W 97.03' #6

Fiberglass Post South 32.99' #9

SURVEY &
REMONUMENTATION

MAR 02 1989

SECTION