

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS

DA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

FEB 28 PM 1 17

For corners in Newaygo (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 14N R 13W L-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

357

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 1, 19 99, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 15, Lincoln Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856
 14" Beech N71°E 26 Links (17.16') #1
 24" White Pine S57°W 29 Links (19.14') #2

Newaygo County Road Commission Sheet
 Railroad Rail 1956
 24" Black Oak N41°W 51.2' #3
 24" White Oak N32°E 37.4' #4
 16" Beech S12°W 71.7' #5

Robert A. Griffin R.L.S. #13584
 1978 Found Iron in center of East and West pavement (did not dig up)
 2" Pipe Street Sign S27°W 25.4' #6
 Red Oak N40°W 52.7' #3

Norman L. Ochs R.L.S. #22439
 January 22, 1985 Drawing Number 85135B
 July 23, 1986 Drawing Number 86146B
 Set P.K. nail (1985) Found P.K. nail (1986)
 24" Black Oak N41°W 51.20' #3
 24" White Oak N32°E 37.40' #4
 16" Beech S12°W 71.70' #5

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found Railroad Rail raised with a 1/2" x 14" Rod, raised with 5/8" x 16" rod, raised with P.K. nail and the centerline of the East and West bituminous road is 1.5 feet ± South and the centerline of the two-track going North is 4 feet ± West. There is no apparent occupation going South. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #5 good condition, #6 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:


Removed P.K. nail and 5/8" x 16" Rod and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" over 1/2" x 14" Rod and Railroad Rail as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

48" Red Oak N40°W 52.7' (has B/T tag) Set spike with tag #22439 in Southwest side of tree (3' ± above grade) #3
 40" White Oak N30°E 38.39' Set spike with tag #22439 in West side of tree. (3' ± above grade) #4
 18" - 22" Twin Beech S10°W 72.27' Set spike with tag #22439 in West side of tree. #5
 6" Red Oak S15°E 70.29' Set spike with tag #22439 in West side of tree.

Signed by Norman L. Ochs Date December 10, 1999
 Norman L. Ochs
 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on December 16, 1999
 Norman L. Ochs, County Representative.



N. L. O.