

**SURVEY & REMONUMENTATION**

MAR 02 1999

**1998 Newaygo County Remonumentation Project**

NEWAYGO COUNTY REGISTER OF DEEDS  
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE '99 FEB 17 PM 3 41  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

**SECTION**

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>13W</u>	<u>I-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Linda M. Brown*

VOL. 2 251

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 16, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southwest Corner, Section 35, Lincoln Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Mullett and Brookfield 1838  
12" Hemlock N80°E 15 Links (9.9') #1  
10" Hemlock N24°W 5 Links (3.3') #2  
Northwest Corner, Section 2, T13N R13W East  
20 Links (13.20')

Lyle S. Shepherd R.L.S. #503  
Book 32, Pages 32 and 33 October 29, 1926  
Well Point  
18" Pine Stump S48½°E 47 links (31.02') #3  
30" Pine Stump S02½°W 47 Links (31.02') #4

William M. Jacques (County Surveyor)  
Book B, Pages 28 and 29 December 1, 1908  
Stake with broken glass around stake.

Ralph A. Smith R.L.S. #3421  
Witness Book Number 1, Page 31 July 7, 1959  
Found 1" Pipe and lode stone  
8" Poplar S10°W 15.5' #5  
Power Pole N80°W 73.9' #6  
16" Red Oak N80°E 130.9' #7

Robert A. Griffin R.L.S. #13584  
LCRC #404 June 7, 1977 Found 1" Gas Pipe  
and witnesses from Smith survey. Replaced with  
5" square X 36" concrete monument  
20" Black Oak N76°E 131.98' #7  
Power Pole N64°W 74.27' #6  
4" X 7' Post North 1.9' #8

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 5" square concrete monument in the centerline of the dirt road going North and in the centerline of the dirt road going East. The condition of the recorded witnesses are: #1 thru #5 gone, #6 good condition, #7 stump, #8 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Accepted 5" square X 36" concrete monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole N58°W 74.27' Found spike in West side of pole. #6  
16" Oak Stump N81°E 131.0' #7  
14" - 14" - 16" Triple Maple (blazed) S55°W 32.57' Found cabin spike in North side of tree.  
8" - 6" Twin Maple (blazed) S46°W 65.0' Found spike with tag #22439 in Northeast side of tree.  
6" Cherry (blazed) N49°E 71.95' Found spike with tag #22439 in West side of tree.  
5" square concrete monument (Northwest Corner, Section 2, T13N R13W) East 13.18'



Signed by Norman L. Ochs Date December 18, 1998  
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on December 22, 1998  
Norman L. Ochs, County Representative.

*M. L. O.*