

SURVEY & REMONUMENTATION

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

00 FEB 28 PM 1 17

For corners in Newaygo (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 14N R 13W J-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

358

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on November 30, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 14, Lincoln Township, Newaygo County, Michigan.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856
 8" White Pine N31°E 17 Links (11.22') #1
 26" White Pine S42°W 2 Links (1.32') #2

Ralph A. Smith R.L.S. #3421
 April 12, 1965

Measured 2563.60 feet from the South One Quarter Corner to the Southeast Corner of Section 14.

Lyle S. Shepherd R.L.S. #503 1915 to 1949
 Witness Book Number 1, Page 38 Narrow Rail
 6" Maple S60°W 52.10' #3
 5" White Oak S45°E 39.7' #4

Newaygo County Road Commission Sheet
 Railroad Rail 1956

5" Jack Pine S42°W 57.9' #5
 18" Twin Red Oak S55°E 68.5' #6
 14" Maple N47°E 76.5' #7

Jack E. Pierson R.L.S. #19305
 August 26, 1981 File Number SAL-092-81
 3/4" Pipe
 18" Maple N49°E 77.36' #7
 24" Twin Red Oak S56°E 69.21' #6
 6" Red Oak S54°W 60.10' #8

OVER ↘

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 24" Railroad Rail 10" ± below grade, raised with a 1/2" x 24" Rerod, raised with a 3/4" x 6" Iron Pipe, on line ± with the centerline of the East and West bituminous road and on line ± with the centerline of the bituminous road going North. There is no apparent occupation going South. The condition of the recorded witnesses are: #1 thru #5 gone, #6 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Railroad Rail, Rerod and Iron Pipe and set a 4" diameter Harrison cast iron monument 30" long marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

24" - 26" Twin Red Oak (blazed) S67°E 69.21' Found nail in Northeast side of tree. #6
 22" Maple (blazed) N45°E 77.30' Found nail in Northwest side of tree. #7
 14" Red Oak (blazed) S52°W 60.07' Found nail in Southeast side of tree. #8
 12" Jack Pine (blazed) S60°W 66.76' Found nail in Southeast side of tree.
 14" White Oak N78°W 204.85' Set spike with tag #22439 in South side of tree.

Signed by Norman L. Ochs Date December 10, 1999
 Surveyor's Michigan License No. 22439



Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on December 16, 1999
 Norman L. Ochs, County Representative.

N.L.O.

A. Description (cont.)

Norman L. Ochs R.L.S. #22439

June 4, 1992 Drawing Number 92181B and October 1, 1996 Drawing Number 96245B

Found ¾" Pipe

18" Maple N49°E 77.36' #7

24" Twin Red Oak S56°E 69.21' #6

6" Red Oak S54°W 60.10' #8

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION