

**SURVEY & REMONUMENTATION**

MAR 02 1999

**1998 Newaygo County Remonumentation Project**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'99 FEB 17 PM 3 41

**SECTION**

For corners in  
Newaygo  
(County)

Located in:

Corner Code #

*Linda M. Brown*

- 1. Public Land Survey      T 14N R 13W      K-3  
    T    R  
    T    R  
    T    R
- 2. Property Controlling    S    T    R  
    in Section                S    T    R
- 3. Miscellaneous            S    T    R  
    Property in Sec.         S    T    R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

VOL. 2

255

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on November 30, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southeast Corner, Section 2, Lincoln Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Milton Nye 1856 Resurvey  
6" White Oak N03°E 23 Links (15.18')#1  
6" White Oak S36°W 22½ Links (14.85')#2

Robert A. Griffin R.L.S. #13584  
LCRC #576 1983 Found Iron object (did not remove) raised with a ½" X 16" Rebar raised with a ½" X 20" Iron Rod raised with a 1" X 9" Iron Rod. Set a 5" X 60" Concrete Monument with brass cap.  
8" Black Oak N13°W 71.33' #5  
5" White Pine N35°E 53.35' #6  
12" White Oak N43°E 84.42' #7  
Fiberglass Post North 38.35' #8

Ralph A. Smith R.L.S. #3421  
Book 46A, Page 6 1950's Oak Stake and ½" Gas Pipe  
15" Black Oak S60°E 54' #3  
14" Black Oak S03°E 46.2' #4

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 5" X 5" concrete monument. The centerline of the East and West bituminous road is 4 feet ± South and the centerline of a two-track going South is 6 feet ± West. There is no apparent occupation going North. The condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #8 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Accepted 5" X 60" Concrete Monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 20" Black Oak (blazed) South 46.34' Set spike with tag #22439 in East side of tree. #4
- 14" Black Oak (blazed) N11°W 71.05' Found dock spike in West side of tree. #5
- 6" Red Pine (blazed) N38°E 53.23' Found dock spike in Westerly side of tree. #6
- 16" White Oak (blazed) N45°E 84.45' Found dock spike in Northwesterly side of tree. #7
- Carsonite Post North 38.4' ± to center. #8

Signed by *Norman L. Ochs*  
Norman L. Ochs

Date December 4, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on December 8, 1998  
Norman L. Ochs, County Representative.

*N.L.O.*

