

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'99 FEB 17 PM 3 42

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 14N R 13W L-13 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. , Recorded Plat 5. Private Claims

Linda M. Brown

VOL. 2

258

Register of Deeds Stamp & File Number

Grid with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, Norman L. Ochs, in a field survey on December 16, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 36, Lincoln Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838 7" Beech N73°W 16 Links (10.56')#1 16" Pine N52°E 14 Links (9.24')#2

Ralph A. Smith R.L.S. #3421 Witness Book Number 1, Page 31 1938 Wagon Skein 8" White Oak N15°±E 35.1' #5 15" White Oak S45°±W 17.6' #4

Lyle S. Shepherd R.L.S. #503 Book 32, Pages 32 and 33 October 27, 1926 Witness Book Number 1, Page 31 Pine Stump N45½°E 44½ Links (29.37')#3 12" White Oak S46°W 27½ Links (18.15')#4

Robert A. Griffin R.L.S. #13584 LCRC #641 1973 Searched but did not find Wagon Skein, but did find the witnesses. Set 5" square X 36" concrete monument. 4" X 7" Pine Post North 32.78' #6 14" White Oak N12°E 35.42' #5 4" Maple N22°W 46.98' #7 24" White Oak S49°W 18.32' #4 North One Quarter Corner, Section 1, T13N R13W, S89°21'30"W 0.62' #8

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 5" square concrete monument. The centerline of the East and West dirt road is 3 feet ± North. The condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 5" square X 36" concrete monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

30" White Oak (blazed) S52°W 18.22' Found spike in Southeasterly side of tree. #4 24" White Oak (blazed) N17°E 35.47' Set spike with tag #22439 in West side of tree. #5 4" X 7" Pine Post North 32.78' Found spike with tag #13584 in East side of post. #6 12" Maple (blazed) N18°W 46.94' Found cabin spike in Northeast side of tree. #7 North One Quarter Corner, Section 1, T13N R13W, Concrete Monument, West 0.62' #8

Signed by Norman L. Ochs Date December 18, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group on December 22, 1998 Norman L. Ochs, County Representative.



N.L.O.