

**SURVEY &
REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

'98 MAR 6 PM 12

Linda M. Brown

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

VOL. 2

114

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>11W</u>	<u>A-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on October 16, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 6, Goodwell Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1838
8" Sugar S21°W 6 Links (3.96') #1
40" Black Oak N21°W 12 Links (7.92') #2

Lyle Shepherd R.L.S. #503
Witness Book Number 1 Page 5 Book 36 Pages 90 and 91
September 6, 1916 Found old stake.
30" Pine Stump N37½°W 37.5'± #3
4" Twin White Oak S67½°W 42.5'± #4

Ronald J. Ruszala R.L.S. #21581
LCRC #369 November 25, 1975
Set 1" Pipe using Government notes, no landmarks present.
20" Twin Maple S89°W 50.12' Set nail and blaze at base.
12" Maple N41°W 70.12' Set nail and blaze.
Northwest leg of tower #4194 S66°E 37.0' at base.

OVER ↵

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 3 foot threaded ¾" Pipe with coupling, 2½" Bolt screwed into end with 1" nut held on by Bolt. The centerline of the North and South Power line two-track is 81 feet East. The centerline of overhead wires are 43 feet East. The East edge of North and South woods line is 45 feet West. The condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

17"-20" Forked Maple (blazed) N87°W 50.13' Found spike in Southeast side of tree and set spike and tag above it. #5
18" Maple (blazed) N38°W 70.07' Found spike in Southwest side of tree and set spike and tag above it. #6
Northwest leg of Electric Tower #4194 S62°E 37.05' #7
20" Maple (blazed) S58°W 63.22' Found spike in North side of tree and set spike and tag above it. #8

Signed by Norman L. Ochs Date November 10, 1997

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on November 11, 1997
Norman L. Ochs, County Representative.

N.L.O.



A. Description (cont.)

Alan L. Meyer R.L.S. #15406

LCRC #998 February 1990

22" Twin Maple West 50.20' Nail and blaze. #5

16" Maple N40°W 70.0' Nail and blaze. #6

Northwest leg of Tower #4194 S66°E 37.0' at base. #7

18" Maple S45°W 63.16' Nail in Westérly root. #8