

**SURVEY & REMONUMENTATION**

1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 117

**COMMISSION**  
For corners in

<u>Newaygo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>11W</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

NEWAYGO COUNTY  
REGISTER OF DEEDS  
MARLENE TOOGOOD

'95 MAR 14 PM 3 56

*Marlene Toogood*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Norman L. Ochs, in a field survey on October 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

NW Corner, Sec. 19, Goodwell Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Hodgson 1837  
12" Beech S32°E 43 lks (28.38') #1  
6" Beech N67°E 43 lks (28.38') #2

Lyle S. Shepherd RLS #503 -OVER-  
Book 36, Pg. 90, Sept. 6, 1916  
14" W. Pine N83-1/2° E 53 ft. #3  
12" W. Pine S36-3/4°E 54.5 ft. #4  
Measured 5288.30 ft. from the SW cor. to the NW cor. of Sec. 19.  
Measured 2640.80 ft. from the W-1/4 cor. to the NW cor. of Sec. 19.  
Measured 2677.80 ft. from the NW cor. to the N-1/4 cor. of Sec. 19 & measured 80 chains (5280 ft.) from the SW cor. to the W-1/4 cor. of Sec. 18

Delos G. Anderson (Co. Surveyor)  
Book A Pg's 221 & 222  
Old Gov't corner

Measured 40 chains (2640 ft.) from the NW cor. to the N-1/4 cor. of Sec. 19 & measured 80 chains (5280 ft.) from the SW cor. to the W-1/4 cor. of Sec. 18

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NW cor. to the NE cor. of Sec. 10.

Found 1/2" rod 3' West of CL N&S road and 2 foot North of CL road going East and found a buried tel. cable 18" deep on South side of our hole running E & W.

Condition of witnesses are: 1 thru 6 gone, 7 is OK, 8 is gone, # 9 & 10 are OK.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1/2" rod and set a 4" dia. Harrison cast iron mon. 20" long and is accepted as a careful and faithful reestablishment of the original corner.

SW leg of Tower N31°E 85.92' Measured 2' above ground #7.  
13" W. Oak N64°W 48.96' Spk. on NE side #9  
8" Red Pine S68°W 63.39' Spk. on N side. #10.  
8" Red Pine S62°E 107.30' Spk. on S. side.



Signed by Norman L. Ochs  
Norman L. Ochs 22439

Date October 19, 1994

Surveyor's Michigan License No. \_\_\_\_\_  
Approved by peer review group on November 10, 1994.  
Norman L. Ochs, County Representative

A Cont.

NCRC Sheet

Iron

SW Leg Tower N23°E 86.0'

T.Pole S51°W 42.1' #8

6" W. Oak N68°W 48.65' #9

6/18/1908 Wm. Jacques

24" Pine Stp. N55°E 39.93'

30" Pine Stp. S13°E 39.93'

May 3, 1978 N.E. & S. Co.

Fnd. 1/2" rod.

10" W. Oak N64°W 48.91' #9

6" R. Pine S68°W 63.36' #10

SW Leg Tower N31°E 85.92' #7