

MAR 02 1999

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'99 FEB 17 PM 3 42

For corners in Newaygo SECTION Located in: Corner Code #
1. Public Land Survey T 14N R 11W F-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Linda M. Brown

VOL. 2 269

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on July 15, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Table with 13 columns (A-M) and 13 rows (1-13) for recording corner points.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 33, Goodwell Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837 William Byl, Inc. February 1988
28" Pine N17 1/2 E 38 Links (25.08') #1 Located Iron with metal detector only measured West 33.10' ± at The North One Quarter corner, Section 4, T13N R11W. #6
24" Pine N07 W 50 Links (33.00') #2
Norman L. Ochs R.L.S. #22439
April 4, 1979 Set 1/2" Rod on woods line and fence going North for occupation which is 3.16 feet West of G.L.O. proration.
4" - 5" Twin Maple S10 ± W 48.5' #3
16" Red Oak N40 ± W 53.78' #4
12" Red Oak N60 ± W 73.50' #5
North One Quarter Corner, Section 4, T13N R11W, West 33.12' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" X 18" Rerod on line ± with edge of woods and field to the North and the centerline of the East and West bituminous road is 2 feet ± South. The condition of the recorded witnesses are: #1 and #2 gone, #3 dead, #4 and #5 stumps, #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rerod and set a 2 3/4" X 20" Harrison cast iron monument marked "County Surveyor" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

10" - 4" Dead Twin Maple S10 W 48.50' Found spike in West side of tree. #3
24" Stump N25 W 54.00' ± to centerline #4
18" Stump N63 W 73.42' Found spike in Easterly side of stump. #5
North One Quarter Corner, Section 4, T13N R11W (2 3/4" X 20" Harrison cast iron monument) West 33.08' #6
6" - 6" - 6" Triple Maple S01 W 51.47' Set spike with tag #22439 in West side of tree.
18" Red Oak (blazed) N63 W 74.62' Set spike with tag #22439 in Southeast side of tree.
8" White Pine (blazed) S53 W 47.08' Set spike with tag #22439 in East side of tree.

Signed by Norman L. Ochs Date November 3, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group on November 10, 1998 Norman L. Ochs, County Representative.



N.L.O.