

**SURVEY &  
REMONUMENTATION**

**APR 04 1996**

**COMMISSION**

**1995 Newaygo County Remonumentation Project**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
MARSHALL TOWNSHIP

93 FEB 21 AM 9 41

*M. L. Ochs*

**VOL. 1 PAGE 184**

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>11W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**Register of Deeds Stamp & File Number**

I, Norman L. Ochs, in a field survey on September 9, 1995, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

N.W. Corner, Section 22, Goodwell Twp., Newaygo Co., MI

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

- G.L.O. J. H. Mullett 1837  
8" Tamarack S24°E 14Lks (9.24')#1  
12" Pine S81°W 35Lks (23.10')#2
- William M. Jacques (Co. Surveyor)  
Book 8 Pg. 75 1904  
Measured 80 ch 53 ft (5333 ft) from the N.E. Cor. to the S.E. Cor. of Sec. 21
- Delos G. Anderson (Co. Surveyor)  
Book A Pg's 257 & 258 May 21-22, 1899  
16" Pine N78°W 32Lks (21.12')#3  
Measured 79.58 ch (5252.28 ft) from the S.E. Cor. to the N.E. Cor. Sec. 16
- William M. Jacques (Co. Surveyor)  
Book 8 Pg. 36 December 20, 1905  
Measured 79:50 ch (5247 ft) from the N.E. cor. to the S.E. Cor. of Sec. 21
- William M. Jacques (Co. Surveyor)  
Reg. of Deeds Book #1 Sept. 22, 1911 Book B Pg. 52  
Stake with broken glass  
Measured 39.88 ch (2632.08 ft) from the S.E. Cor. to the S ¼ Cor. of Sec. 16 and measured 79.76 ch (5264.16 ft) from the S.E. Cor. to the S.W. Cor. of Sec. 16 and measured 39.80 ch (2626.8 ft) from the S.E. Cor. to the E ¼ Cor. of Sec. 16 and measured 79.6 ch (5253.6 ft) from the S.E. Cor. to the N.E. Cor. of Sec. 16
- William M. Jacques (Co. Surveyor)  
Book 23 Pg. 10 July 1, 1907  
Measured 78.50 ch (5181 ft) from the N.W. Cor. to the N.E. Cor. of Sec. 22
- Lyle S. Shepherd RLS #503  
Book 49 Pg. 40 May 1921  
Cor. fence post N46°45'W 44.8' #4  
18" Pine Stp. S61°15'W 84.6' #5

OVER 6

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found ¾" Pipe raised with 1" Pipe, glass and a 1½"x16" strap iron and the centerline of N&S road is 1 ft East and road going West is 4 ft South and there is a stump fence row going East. I measured 2652.30 ft from the N.W. Cor. to the N. ¼ Cor of Sec. 22 and the condition of the recorded witness are: #1 thru #6 gone, #7 good condition, #8 and #9 gone, #10 and #11 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed ¾" pipe, 1" pipe, glass and 1½"x16" strap iron and set a 4" dia. Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner, in the same location as the ¾" pipe.

- P. Pole N46°W 72.60' Spike in East side of pole. #7
- 24" W. Oak S50°W 113.42' Spike in North side of tree. #10
- P. Pole S45°W 95.14' Spike in South side of pole. #11
- 12" Spruce S50°W 75.61' P.K. in South side of tree.

Signed by *Norman L. Ochs* Date September 11, 1995

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors



Approved by Peer Review Group On October 3, 1995  
Norman L. Ochs, County Representative.

*N. L. O.*

A. Description .... (Continued)

Lyle S. Shepherd RLS #503

Book B Pg's 86 & 87 May 2, 1934 and Book 70A Pg. 3

Witness Book No. 1 Pg. 6

Iron

Corner fence post N46°W 44.8' #4

18" Pine Stp. S61°15'W 84.4' #5

6" W. Oak N38°W 51.3' #6

Measured 2624.32 ft from the N.E. Cor. to the N. ¼ Cor. of Sec. 21 and measured 5248.62 ft from the N.E. Cor. to the N.W. Cor. of Sec. 21 and measured 2656.99 ft from the N.E. Cor. to the E. ¼ Cor. of Sec. 21 and measured 5308.99 ft from the N.E. Cor. to the S.E. Cor. of Sec. 21

C. Zimmerman PE #07301 1951

Iron

P. Pole N46°W 71.5' #7

12" Oak S42°W 77.0' #8

N.E. Cor. Hse. S50°W 144.1' #9

NCRC Sheet

Iron

P. Pole N46°W 71.5' #7

12" Oak S42°W 77.0' #8

N.E. Cor. Hse. S50°W 144.1' #9

Patrick A. Salisbury RLS #13594

Drawing No. 73006B February 2, 1973

Drawing No. 75011B February 6, 1975

Found ¾" Pipe Stump fence going East

20" W. Oak S35±°W 113.45' #10

P. Pole S45°W 95.18' #11

P. Pole N46°W 72.00' #7

Measured 2624.26 ft from the N.E. Cor. to the N. ¼ Cor. of Sec. 21 and measured 5248.52 ft from the N.E. Cor. to the N.W. Cor. of Sec. 21 and measured 2653.48 ft from the N.E. Cor. to the E. ¼ Cor. of Sec. 21

Newaygo Engineering and Survey Co.

Drawing No. 78005B&D October 9, 1978

Found ¾" Pipe

20" W. Oak S57°W 113.44' #10

P. Pole S71°W 95.06' #11

P. Pole N43°W 72.43' #7

Measured 2619.12 ft from the S.E. Cor. to the E. ¼ Cor. of Sec. 16 and measured 2624.26 ft from the S.E. Cor. to the S. ¼ Cor. of Sec. 16