

MAR 02 1999

SECTION

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE, FILING REQUIREMENT of Act 74, Mich. P.A. 1970

99 FEB 17 PM 3 42

For corners in Newaygo (County)

Located in:

Corner Code #

Linda M. Brown

1. Public Land Survey

T 14N R 11W

G-13

VOL. 2

270

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on July 15, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 33, Goodwell Township, Newaygo County, Michigan.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837 10" White Oak N06°W 16 Links (10.56')#1 10" White Oak N47°E 25 Links (16.5')#2

Ralph A. Smith R.L.S. #3421 and Newaygo County Road Commission Sheet Iron Field Book 70 Page 137 August 8, 1951 20" Maple N10°E 61.4' #3 16" White Oak S10°W 38.5' #4 18" White Oak S30°W 45.9' #5 Northeast Corner, Section 4, T13N R11W, West 46.20' #6

Norman L. Ochs R.L.S. #22439 September 8, 1978 Found 3/4" Square Iron Northwest Corner, Section 3, T13N R11W, West 46.20' #6 16" White Oak Stump S10°W 38.5' #4 18" White Oak Stump S30°W 45.7' #5 28" Maple N10°E 61.5' #3

William R. Byl R.L.S. #23502 February 1988 Located iron with metal detector only measured West 46.2 feet to Northwest Corner, Section 3, T13N R11W.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" X 1" X 15" Rod. The tree line and edge of woods going North is 25± East. The centerline of the East and West bituminous road is 1 foot South. The condition of the recorded witnesses are: #1 and #2 gone, #3 good condition, #4 gone, #5 stump, #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rod and set a 2 3/4" X 20" Harrison cast iron monument marked "County Survey" in new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

30" Maple N10°E 62.54' Set spike with tag #22439 in West side of tree. #3 Stump decayed S30°W 46.00± #5 Northeast Corner, Section 4, T13N R11W (2 3/4" X 20" Harrison cast iron monument) West 46.20' #6 12" Red Oak N27°W 58.83' Set spike with tag #22439 in East side of tree. 4" White Pine (blazed) S23°E 36.90' Set spike with tag #22439 in West side of tree. 6" White Oak (blazed) S32°W 40.47' Set spike with tag #22439 in East side of tree.

Signed by Norman L. Ochs Date November 5, 1998

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors

Approved by Peer Review Group on November 10, 1998 Norman L. Ochs, County Representative.

N.L.O.

