

1993

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 PM 3 27

COMMISSION

For corners in

Newaygo

(County)

Located In:

Corner Code ##

- | | | | | | |
|---------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 14N | R | 12W | A-1 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

Marlene Toogood

VOL 001 PAGE 41

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on December 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NW Corner, Section 6, Wilcox Twp.

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. John Hodgson 1973 New. Eng. & Sur. Co.
 - 12" Pine S45°W 57 Lks #1 Fnd. 3/4" Pipe
 - 13" Pine N5°E 26 Lks #3 18" Oak N50°W 28.04' #5
 - No. 1, Pg.15 15" Oak S05°E 26.07' #6
 - Lyle Shepherd's Wit. Book/ 24" Oak N70°E 53.01' #7
 - 24" Pine Stp S8°30'E 34+ #3
 - 30" Pine Stp N28°E 33'+ #4

1973 Clint Cole RLS#17615
 Fnd. same 3/4" Pipe & wit.
 as N.E.&S. See survey
 recorded in Series G-9131

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 In 1993 New. Eng. & Sur. Co. found a 3/4" pipe, honored for Section corner, removed the 3/4" pipe and replaced with 4" cast iron Harrison monument.

Condition of recorded witnesses is: #1, gone, #3 gone, #3 gone, #4 gone, #5 good condition, #6 good condition, #7, good condition.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Accepted 4" Harrison cast iron monument as a substantial marker for the section corner and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 16" B. Oak S0°E 25.99' Nail in East side of tree #6.
- 20" B. Oak N49°W 27.73' Nail in SW side of tree #5.
- 11" W. Oak N9°W 23.36' Nail in East side of tree
- 26" B. Oak N69°30' E 53.30' Nail in SW side of tree #7.



Signed by Norman L. Ochs
 Norman L. Ochs 22439

Date December 15, 1993

Surveyor's Michigan License No. _____
 Approved by Peer Review Group Dec. 21, 1993
 Norman L. Ochs, County Representative