

**SURVEY &
REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

'98 MAR 6 PM 12 36

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

Linda M. Brown

VOL. 2

109

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>12W</u>	<u>C-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman L. Ochs, in a field survey on December 3, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 5, Wilcox Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837
8" White Oak S20°E 20 Links (13.2') #1
36" Pine S66°W 24 Links (15.84') #2

Ralph A. Smith R.L.S. #3421
November 1963 Witness Book Number 1 Page 15
Book 88 Page 26 Set ¾" Pipe
12" Red Oak S62°E 24.2' #3
12" Red Oak N10°E 37.1' #4
5" White Oak N42°W 34.9' #5
16" White Oak S35°W 24.5' #6

Delos G. Anderson (County Surveyor)
January 29, 1900 Book A Pages 289 and 290
Old Government Corner
Pine Witness there

Clinton E. Cole R.L.S. #17615
File Number 2300-74 November 5, 1974
Gives no witnesses.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found ¾" X 22" Iron Pipe (pinched on bottom) with cap #17615 in centerline of the East and West dirt road and in centerline of two-track going South. The remnants of fence going South is 15 feet East. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed ¾" Iron Pipe and set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.
16" Red Oak (blazed) S60°E 24.20' Set spike and brass washer in North side of tree. #3
20" Red Oak (blazed) N12°E 37.72' Set spike and brass washer in West side of tree. #4
10" White Oak (blazed) N42°W 34.90' Set spike and brass washer in Northeasterly side of tree. #5
10" White Oak (blazed) S35°W 24.90' Set spike and brass washer in Northwesterly side of tree. #6
Southwest Corner, Section 32, T15N R12W, 4" Harrison Monument West 29.05'

Signed by Norman L. Ochs Date December 15, 1997

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on December 18, 1997
Norman L. Ochs, County Representative.

N.L.O.

