

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**1996 Newaygo County Remonumentation Project**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

97 FEB 12 PM 4 45

*Linda M. Brown*

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>12W</u>	<u>G-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2 PAGE 7

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Norman L. Ochs, in a field survey on October 2, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Northwest Corner, Section 3, Wilcox Township, Newaygo County, Michigan

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John Hodgson 1838  
18" Hemlock S43°E 27 Links (17.82')#1  
8" Hemlock S40°W 17 Links (11.22')#2

Robert A. Griffin R.L.S. #13584 1981  
Set 10" Dock Spike 26.4 feet East of Southwest Corner,  
Section 34, T15N R12W  
6" White Pine N32°W 54.15' #3  
Gate Post N02°E 34.29' #4

Lyle S. Shepherd R.L.S. #503 November 17, 1940  
Book 81C Page 5 Did not find. Found Corner for township North and measured East from this corner 26.4' and set flag 1" X 2' Iron Bar

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found large spike set by Robert A. Griffin in the centerline of road going South and the centerline of road going East and West is 3 feet South and the centerline of drive going North is 7 feet West and the condition of the recorded witnesses are: #1 and #2 gone, #3 good condition, #4 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed large spike and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" in the exact location as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

20" White Pine N32°W 54.27' Set spike and tag in Southwest side of tree. #3  
1½" Well Point (Southwest Corner, Section 34, T15N R12W) West 26.45' Found spike inside.  
6" Red Pine S55°E 58.20' Set spike and tag in Northeast side of tree.  
Power Pole N45°W 45.0' Set spike and tag in Southwest side of pole.  
2½" Pipe (brace for gate) S35°W 62.02' Center

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996  
Norman L. Ochs, County Representative.

*N. L. O.*

