

SURVEY & REMONUMENTATION

APR 04 1996

1995 Newaygo County Remonumentation Project

COMMISSION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY
REGISTER OF DEEDS
MARION T. JOHNSON

95 FEB 21 AM 9 41

Madeline Trogel

VOL. 1 PAGE 187

Register of Deeds Stamp & File Number

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>12W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Norman L. Ochs, in a field survey on June 26, 1995, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

N.W. Corner, Section 34, Wilcox Twp., Newaygo Co., MI

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Mullett 1837
12" Beech N63°E 45Lks (29.7")#1
24"Hemlock S57°E 30Lks (19.8")#2

N.C.R.C. Sheet
1 1/2" Pipe
40" Pine Stp. N37°W 66.0' #6
Apple S74°W 48.6' #7
24" Pine Stp. S82°E 66.6' #8

Ralph A. Smith RLS #3421 May 1958
Book 68 Pg. 73 1 1/2" Gaspipe
T. Pole S45°E 60.1' #3
T. Guy Pole N35°E 56.2' #4
14" Elm S30°W 63.6' #5
Measured 2639.10 ft from the N.E. Cor. to the E. 1/4 Cor. of Sec. 33 and measured 2648 ft from the N. 1/4 Cor. to the N.E. Cor. of Sec. 33

Newaygo Engineering and Survey Co.
July 25, 1977 Section break of Sec. 33
Found 1" rod
Measured 2602.30 ft from the N. 1/4 Cor. to the N.E. Cor. of Sec. 33 and
Measured 2639.21 ft from the N.E. Cor. to the E. 1/4 Cor. of Sec. 33

Newaygo Engineering and Survey Co.
January 20, 1992
Found 3/4" rod in centerline of N & S blacktop road and in centerline of gravel road going East
P. Pole N45°W 73.40' #9
Riser N45°E 51.45' #10
10" Maple S70°W 77.44' #11
4" Ash S35°E 93.77' #12
Measured 2654.29 ft from the N.W. Cor. to the N. 1/4 Cor. of Sec. 34 and measured 2639.22 ft from the N.W. Cor. to the W. 1/4 Cor. of Sec. 34

Newaygo Engineering and Survey Co.
June 29, 1982 Section break Section 28
Measured 2658.44 ft from the S.E. Cor. to the E. 1/4 Cor. of Section 33

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" rod and well point in the centerline of N&S road and in the centerline of road going to the East. I measured 2654.64 ft from the N.W. Cor. to the N. 1/4 Cor. of Sec. 34 and the condition of the recorded witnesses are: #1 thru #8 gone, #9 good condition, #10 gone, #11 and #12 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1" rod and well point and set a 4" dia. Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

P. Pole N45°W 73.47' Spike in Northeast side of pole. #9
10" Maple S70°W 77.47' Spike in North side of tree. #11
6" Ash S35°E 93.75' Spike in West side of tree. #12
S.W. Cor. conc. base (3.3' E&W by 4.3' N&S) @ telephone riser N45°E 59.68'

Signed by Norman L. Ochs Date September 11, 1995

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1997
Revised Major 1997
Revised Jan., 1983



Approved by Peer Review Group On October 3, 1995
Norman L. Ochs, County Representative.

MLO