

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY
 REGISTER OF DEEDS
 MARLENE TOOGOOD

JAN 21 PM 3 27

For corners in

Newaygo (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>12W</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Marlene Toogood
VOL 001 PAGE 44

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- SE Corner, Section 33, Wilcox Twp.
 A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. 1953 R.A. Smith #3421 03-06-93 New Eng. & Survey Co. found 5/8" Rod.
 - 14" Hemlock N42oE 15 LKS #1 Field Book 68 Pg 73 Iron PK Nail West 19.80' (NE cor. sec. 4 Everett Twp.)
 - 8" Hemlock N24oW 33 LKS #2 P.Pole S 55oW 50.45' #5
 - Lyle S. Shepherd #503 T.Pole N25oW 63.2' #6
 - Field Book 70 Pg. 46 11-15-77 New. Eng. & Sur. CO. 14" Elm S23oW 46.14' #8
 - IRON FD 1/2" Rod P.Pole S 56oW 53.71' #5
 - Stone "x" N47 1/2oE 30.8' #3 P.Pole S55oW 51.11' #5 Top center Tel. Riser S 40oE 41.85' #7
 - Stone point N 48 3/4oW 29.0' #4 Tel. Riser S33oE 39.60' #7 Tel. Riser N45oW 69.94' #9
 - June 12, 1930

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 In 1930 Lyle S. Shepherd broke the SE 1/4 of sec. 33, Wilcox Township. He found the NE corner of section 4, Everett Township to be West 19.80 ft. Shepherd measured 2654.1 ft from the SE corner to S 1/4 corner and measured 2651.40 ft from the SE corner to the E 1/4 corner. In 1953 Ralph A. Smith found an Iron. He measured 2654.10 ft. from the SE corner to the S 1/4 corner and measured 2651.40 ft. from the SE corner to the E 1/4 corner. Smith also found the NE corner of Sec. 4, Everett Twp. to be West 19.80 ft. from the SE corner of section 33. In 1977, I, Norman L. Ochs found 1/2" rod. I measured 2657.07 ft from the SE corner to the S 1/4 corner and measured 2653.67 ft. from the SE corner to the E 1/4 corner in March of 1993. I found 5/8" Rod. In Dec. 1993 I, Norman, L. Ochs, found 1/2" Rod. I replaced it with a 4" Harrison Cast Iron Monument.

Condition of recorded witnesses is; #1 thru #4 Gone, #5 Good condition, #6 Gone, #7 thru #9 Good condition.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Accepted 4" Harrison Cast Iron Monument as a substantial marker for the section corner and is accepted as a careful and faithful re-establishment of the original corner.
 14" Elm S23oW 46.12' Spike in East side of tree #8.
 P.Pole S56oW 53.71' Spike in NW side of Pole #5.
 Top center Tel. Riser S40oE 41.81' #7
 Tel Riser N 45oW 69.89' #9



Signed by Norman L. Ochs Date December 28, 1993
 Norman L. Ochs
 Surveyor's Michigan License No. 22439
 Approved by Peer Review Group on December 29, 1993
 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

SURVEY & REMONUMENTATION
 DEC 27 2000
 SECTION