

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 14N R 12W H-1
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2 PAGE 8

Register of Deeds: Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12							
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36						
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 2, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 3, Wilcox Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Corner not set

Lyle S. Shepherd R.L.S. #503
 Book 81C Page 5 November 17, 1940
 Found 1/2" Iron Rod
 Power Pole N50°W 79.8' #1
 Fence Post South 26.6' #2
 Pine Stump S25°E 97.6' #3
 Telephone Pole S60°E 36.8' #4

N.C.R.C. Sheet
 1/2" Iron
 Power Pole N50°W 79.8' #1
 Telephone Pole S60°E 36.8' #4
 Pine Stump S25°E 97.6' #3
 Fence Post South 24.6' #2

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 3/4" Rod in centerline of East and West road and on fence line going South and the condition of the recorded witnesses are: #1 gone, #2 good condition, #3 found remains of stump, #4 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 3/4" Rod and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Fence Post South 26.6' Face #2
 Telephone Pole N56°W 78.39' Set spike and tag in Southwest side of pole.
 12" Red Pine N01°W 51.37' Set spike and tag in West side of tree.
 24" Red Oak S03°W 95.57' Set spike and tag in East side of tree.
 8" Cherry S35°E 80.01' Set spike and tag in East side of tree.

Signed by Norman L. Ochs Date October 17, 1996
 Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996
 Norman L. Ochs, County Representative.

N. L. O.

