

**SURVEY & REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'98 MAR 6 PM 12 37

*Linda M. Brown*

SECTION

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>12W</u>	<u>H-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____

VOL. 2

113

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Norman L. Ochs, in a field survey on January 10, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

South One Quarter Corner, Section 34, Wilcox Township, Newaygo County, Michigan.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John Hodgson 1837  
13" Beech N43°E 80 Links (52.8') #1  
16" Maple N15°W 27 Links (17.82') #2

Newaygo Engineering and Survey Company  
February 24, 1978 Section Break Found 5/8" Rod  
Concrete Monument North 33.00' #6  
Clump Maple N61°W 72.12' #7  
14"-14"-14" Triple Maple S44°E 52.71' #3

Ralph A. Smith R.L.S. #3421  
January 17, 1956 Book 70 Page 149 Iron  
(3) 10" Maple S50°E 52.2' #3  
12" Maple S06°E 31.3' #4  
(2) 12" Cherry N62°E 67.5' #5

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 3/4" X 24" Rerod in centerline of East and West bituminous road. The remnants of fence line going North is 2 feet West. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #7 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed 3/4" Rerod and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 20" Maple (blazed) S51°E 52.58' Set nail in Northerly side of tree. #3
- 26" Maple (blazed) S05°E 32.13' Set spike and brass washer #22439 in West side of tree. #4
- 14"-14" Twin Cherry (blazed) N63°E 67.90' Set spike and brass washer #22439 in Northwesterly side of tree. #5
- 4" Concrete Monument North 33.00' #6
- 24"-16"-16"-12" Quadruple Maple (blazed) N61°W 72.03' Set nail in Southwesterly side of tree. #7
- 4" diameter Harrison cast iron monument (North One Quarter Corner, Section 3, T13N R12W) West 22.44' #8

Signed by Norman L. Ochs

Date December 15, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on December 18, 1997  
Norman L. Ochs, County Representative.

*N.L.O.*

