

1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 120

For corners in

Newaygo (County)	Located In:	Corner Code ##
1. Public Land Survey	T 14N R 12W	I-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

NEWAYGO COUNTY  
REGISTER OF DEEDS  
MARLENE TOOGOOD

'95 MAR 14 PM 3 57

Register of Deeds Stamp & File Number  
*Marlene Toogood*

I, Norman L. Ochs, in a field survey on October 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.  
NW Corner, Section 35, Wilcox Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. J.H. Mullett 1837  
18" Maple S7°E 137 lks. (90.42') #1  
18" Elm N2°W 105 lks (69.30') #2

Measured 2654.85 ft. from the NE cor. to the N-1/4 cor. of Sec. 34. Measured 2663.70 ft. from the NE cor. to the E-1/4 cor. of Sec. 34. Measured 5332.66 ft. from the NE cor. to the SE cor. Sec. 34. Measured 2656.94 ft. from the NW cor. to the N-1/4 cor. of Sec. 35.

August 26, 1977 N.E. & S. Co.  
Fnd. 1/2" rod AND  
18" W. Oak S17°W 97.87' #5  
Tel. Riser S61°W 43.46' #6  
12"-16" Clp. Maple N75°W 124.75' #7  
28" Elm Stp. N76°W 119.10' #4

-OVER-

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10/27/94 Fnd. 5/8" rod and 1/2" rod.

In Oct., 1994, I, Norman L. Ochs, found 5/8" iron pipe and raised with a 1/2" rod. Replaced with 4" Harrison cast iron monument in the exact location. I measured 2657.26 feet from the NW corner to the N-1/4 corner of Section 35.

Condition of recorded witnesses is: #1 thru #4 gone, #5 thru #9 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10/27/94 Removed rod and set a 4" dia. cast iron Harrison mon. 20" long as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Spk. on W. side 24" W. Oak S17°W 97.89' #5  
Spk. on W. side Clmp. Maple 12"-22" N75°W 124.75' #7.  
Top CL of Tel. Riser S61°W 43.57' #6.  
SE Cor. Hse N38°W 160.79' #9.  
SW Cor. Hse N43°W 186.48' #8.



Signed by Norman L. Ochs Date October 31, 1994

Surveyor's Michigan License No. 22439

Approved by Peer Review Group on November 3, 1994.

Norman L. Ochs, County Representative.

*N.L.O.*

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

SURVEY &  
REMONUMENTATION

DEC 07 2000

SECTION

cont.

985 Wm. Fries, Jr. RLS #30389  
nd. 5/8" iron LCRC #'s 648 & 654 & 709  
8" W. Oak AZ 192° 97.90' #5  
2" Tri. R. Maple AZ 280° 124.70' #7  
W Cor. Hse #3167 AZ 317° (N47°W) 186.52' #8  
E Cor. Hse #3167 AZ 332° 160.78' #9  
Measured 2656.01 ft. from the NE cor.  
to the N-1/4 cor. of Sec. 34. Measured  
664.07 ft. from the NE cor. to the E-1/4  
cor. of Sec. 34.

LCRC Sheet	Measured 2655.0 ft. from the NE cor. to
1/2" Iron (Approx.)	the N-1/4 cor. of Sec. 34, Measured 2657.30
1. Pole N72°W 90.95'	ft. from the NW cor. to the N-1/4 cor. of
8" Elm. N76°W 119.10' #4	Sec. 35 and measured 2663.70 ft. from the
8" W. Oak S14°W 97.3' #5	NW cor. to the W-1/4 cor. of Sec. 35.

SURVEY &  
REMONUMENTATION

JEC 07-2000

SECTION