

**SURVEY & REMONUMENTATION**

MAR 02 1999

**1998 Newaygo County Remonumentation Project**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'99 FEB 17 PM 3 42

*Linda M. Brown*

**SECTION**

For corners in  
Newaygo  
(County)

Located in:

Corner Code #

- |                                       |                           |             |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey                 | T <u>14N</u> R <u>12W</u> | <u>I-13</u> |
|                                       | T ___ R ___               | _____       |
|                                       | T ___ R ___               | _____       |
|                                       | T ___ R ___               | _____       |
| 2. Property Controlling in Section    | S ___ T ___ R ___         | _____       |
|                                       | S ___ T ___ R ___         | _____       |
| 3. Miscellaneous Property in Sec.     | S ___ T ___ R ___         | _____       |
|                                       | S ___ T ___ R ___         | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                           |             |
| 5. Private Claims _____               |                           |             |

VOL. 2

259

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 26, 19 98, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southwest Corner, Section 35, Everett Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John Hodgson 1837  
12" Beech N08½°E 25 Links (16.5') #1  
12" Maple N71°W 14 Links (9.24') #2  
Northeast Corner, Section 3, T13N R12W,  
West 33 Links (21.78') #9

Ralph A. Smith R.L.S. #3421  
Book 70 Page 149 Iron  
12" Maple S72°E 85.7' #3  
16" Oak N66°E 75.4' #4  
10" Maple N34°W 44.1' #5

Newaygo Engineering and Survey Company  
December 20, 1977 Drawing Number 77175B  
¾" Pipe  
Telephone Riser S20°E 40.66' #6  
Southwest Corner House N01°E 74.87' #7  
Southeast Corner House N33°E 91.74' #8  
Northeast Corner, Section 3, T13N R12W, West 21.78' #9

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found ¾" X 9" Iron Pipe and the centerline of the East and West bituminous road is 1 foot North. There is no apparent occupation going North. The condition of the recorded witnesses are: #1 thru #5 gone, #6 newer switching station, #7 thru #9 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed Iron Pipe and set a 2¾" X 20" Harrison cast iron monument marked "County Survey" in a new 8" diameter monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Southwest Corner House Foundation N01°E 74.77' #7  
Southeast Corner House Foundation N33°E 91.70' #8  
Northwest Corner, Section 2, T13N R12W, West 21.74' #9  
Northwest Corner switching station pad (fiber glass) S15°E 44.71'  
Power Pole (WC1 / 12C / 21) S34°W 108.02' Found spike in Southeasterly side of pole.

Signed by Norman L. Ochs Date November 3, 1998  
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors

Approved by Peer Review Group on December 8, 1998  
Norman L. Ochs, County Representative.

*N.L.O.*

