

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Newaygo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>12W</u>	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL **001** PAGE **121**

NEWAYGO COUNTY
 REGISTER OF DEEDS
 MARLENE TOOGOOD

'95 MAR 14 PM 3 57

Register of Deeds Stamp & Fee Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


N-1/4 Corner, Section 35, Wilcox Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:
 GLO J.H. Mullett 1837 #1 August 29, 1977 N.E.&S. Co. NE Cor. School S65°W 93.08' #5
 6" Beech S10°E 11 lks (7.26') Found 1/4" rod Measured 2656.94 ft. from the N-1/4 cor. to the NW cor. of Sec. 35
 6" Beech N35°E 16 lks (10.56') 28" Maple S05°E 125.17' #3 P.Pole N38°W 47.21' #4
 NCRC Sheet NE Cor. Hse S63°W 93.10' #5. Measured 2657.30 ft. from the NE Cor. to the NW cor. of Sec. 35
 T.Pole N39°W 60.5' #6 N. 1/4 cor. to the NW cor. of Sec. 35. Measured 2664.44 ft. from the N-1/4 cor. to the NW cor. of Sec. 35.
 30" Maple S03°E 123.90' #3 35. Measured 5379.50 ft. from the N-1/4 cor. to the S-1/4 cor. of Sec. 35.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 In October, 1994, I, Norman L. Ochs, found a 1/2" rod, 1-1/4 well point, and stone. I measured 2657.26 ft. from the NW cor. to the N-1/4 cor. of Section 35 and measured 2629.95 ft. from the N-1/4 cor. to the NE Corner of Section 35.

Condition of recorded witnesses is: #1 and #2 gone, #3 stump, #4 thru #6 gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Removed 1/2" Rod and set a 4" dia. Harrison Cast Iron mon. 20" long in the exact location and is accepted as a careful and faithful reestablishment of the position of the original corner.
 Spk. on W. side 8" R. Pine N40°E 58.48'
 Spk. on Nly side P.Pole N70°E 150.37'
 Spk. on N. side P.Pole S70°W 159.25'
 Tel. Riser top center N45°W 47.09.
 28" Maple Stp. S05°E 125.22' Spk. on E. side of tree #3.



Signed by Norman L. Ochs Date November 3, 1994
 Surveyor's Michigan License No. 22439
 Approved by Peer Review Group on November 3, 1994.
 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

SURVEY & REMONUMENTATION

JEG 07 2000

SECTION