

**SURVEY &  
REMONUMENTATION**

1994 NEWAYGO COUNTY REMONUMENTATION PROEJCT

MAY - 1 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

NEWAYGO  
(County)

Located In:

Corner Code ##

- |                                       |                           |             |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey                 | T <u>14N</u> R <u>12W</u> | <u>K-11</u> |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                           |             |
| 5. Private Claims _____               |                           |             |

VOL **001** PAGE **122**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
MARLENE TOOGOOD

'95 MAR 14 PM 3 57

*Marlene Toogood*  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on October 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

NE Cor., Section 35, Wilcox Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

GLO J.H. Mullett 1837  
18" B. Ash S50°E 25 lks (16.5') #1  
18" B. Ash N35°W 21 lks (13.86') #2

N.E. & S. Co.

Measured 2630.17 ft. from the NW cor. to the N-1/4 cor. of Sec. 36 and measured 2669.46 ft. from the NW cor. to the W-1/4 cor. of Sec. 36.

April 27, 1981 Jack E Pierson  
RLS 19305 1/2" Rebar Set  
N. End culv. N09°E 25.73' #3 ..... and  
S. End culv. S21°W 18.07' #4

Measured 2630.18 ft. from the NW cor. to the N-1/4 cor. of Sec. 36 and measure 2669.46 ft. from the NW cor. to the W-1/4 cor. of Sec. 36.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On October 27, 1994, I, Norman L. Ochs, found a 1/2" iron replaced with 4" Harrison cast iron monument in the exact location. I measured 2629.95 feet from the NE cor. to the N-1/4 cor. of Sec. 35.

Condition of recorded witnesses is: #1 and #2 gone, #3 and #4 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted a 4" Harrison cast iron monument 20" long as a substantial marker for the Section corner and is accepted as a careful and faithful reestablishment of the original corner.

Fnd. 1/2" rod + 1' E. of C.M.P. Removed, set Harrison monument.  
Spk. on S. side Clm. Map 4"-5" N75°E 109.66'.  
Spk. on S. side 12" Willow N75°W 183.63'.  
N. End C.M.P. N09°W 25.93' #3.  
S. End C.M.P. S21°W 18.15' #4

Signed by Norman L. Ochs

Date November 3, 1994

Surveyor's Michigan License No. 22439

Approved by Peer Group on November 3 1994.  
Norman L. Ochs, County Representative.

*N.L.O.*

