

SURVEY & REMONUMENTATION

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

00 FEB 28 PM 1 17

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>12W</u>	<u>L-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Linda M. Brown
VOL. 2 352

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on July 1, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 24, Wilcox Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. J.H. Mullett 1837
10" Maple N39°E 10 Links (6.60') #1
10" Beech S10°E 17 Links (11.22') #2

Norman L. Ochs R.L.S. #22439
October 17, 1998 Established position of corner equal distance and on line between the Southeast and Southwest Corners. This position fits good with the centerline of an East and West gravel road and with a fence to the North. Set a 1/2" x 18" Rerod with cap #22439 on line ± with the West edge of a pine plantation going South.
18" Red Pine (blazed) South 40.08' #3
18" Red Pine (blazed) N26°E 51.35' #4
36" White Oak (blazed) N53°W 41.15' #5
36" White Oak (blazed) N67°E 74.60' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rod with cap #22439 in centerline of the East and West gravel road and on woods line going North and going South. The fence going North is 2 feet ± West. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1/2" Rod and cap and set a 4" diameter Harrison cast iron monument, 18" long marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the original corner.

18" Red Pine South 40.08' Found spike with tag #22439 in West side of tree. #3
18" Red Pine N26°E 51.35' Found spike with tag #22439 in Northwest side of tree. #4
36" White Oak N53°W 41.15' Found spike with tag #22439 in Northeast side of tree. #5
36" White Oak N67°E 74.60' Found spike with tag #22439 in South side of tree. #6

Signed by Norman L. Ochs Date August 16, 1999
Norman L. Ochs
Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on October 28, 1999
Norman L. Ochs, County Representative.



N. L. O.