

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'94 JAN 21 PM 3 27

For corners in
Newaygo

(County)

Located In:

Corner Code -#

- 1. Public Land Survey T 14N R 14W B-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Marlene Toogood

VOL 001 PAGE 37

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	•												
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 16, 1993,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

B-5, S-1/4 Corner, Section 7, Denver Township

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. Milton Nye 1857 Air photos, from 1930's show road
N35°W 8" Beech 12 lks. grades to N,S, W, & E at approximate
S14°W 14" Beech 9 lks. corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Norman L. Ochs, #22439 and LS, W. Fries, 30389, November 12, 1993, using a large grader from Newaygo County Road Commission, carefully excavated near corner, found a wood stake roughly 2" x 2" x 8" long, pointed. Presumed to be original stake, or petuation of same. On December 16, 1993, replaced the wood stake, set 4" diameter by 18" long cast iron marker for corner. Corner is 6" West of occupied centerline roadway to North and is 5' South of occupied centerline East-West roadway.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 4" Harrison Cast Iron Marker as a substantial marker for the Section corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 4" Cast Iron Marker
- AZ 17° 18" Oak NIR 81.24'
- AZ 151° 5" Cherry 86.65'
- AZ 314° 6" White Oak 40.78'
- AZ 346° 16"-16" Db1. Beech NIR 78.41'

NIR: Nail driven in vertically into exposed tree root. Azimuths are shown above.

Signed by Norman L. Ochs
Norman L. Ochs
Surveyor's Michigan License No. 22439

Date December 27, 1993

Approved by Peer Review Group on December 27, 1993.
Norman L. Ochs, County Representative