

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>14W</u>	<u>K-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2 PAGE 17

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Norman L. Ochs, in a field survey on October 2, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 13, Denver Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye, Mullett and Brookfield Resurvey 1857
20" Maple N73°E 22 Links (14.52')#1
24" Maple S47½°W 39 Links (25.74')#2
16" Maple N43°W 53 Links (34.98')#3

NCRC Sheet Monument
6" Twin Maple S85°E 34.83' #4
8" Maple N43°E 55.83' #5
8" Maple S27°W 42.03' #6

Delos G. Anderson (County Surveyor)
Book A Page's 341 and 342 March 1902
Found Government witnesses

George M. Blass R.L.S. #5489
LCRC #266 June 23, 1961

Located corner site from aerial photograph and government notes. Found pointed rock buried in center of earth grade North and South in line with old logging road West (partially graded). Set a 6" X 5' reinforced concrete monument with brass tablet.

6" Twin Maple S85°E 34.83' #4
8" Maple N43°30'E 55.83' #5
8" Maple S27°30'W 42.03' #6
6" Elm S52°30'W 29.14' #7

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found George M. Blass's 6" diameter concrete monument broken off, 2 feet remaining in ground and the centerline of the North and South road is 1 foot West and the condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #6 good condition, #7 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed remaining concrete monument and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

14"-10" Twin Maple S81°E 35.19' Set spike with tag in North side of tree. "Re-blazed" #4
16" Maple N48°E 56.05' Set spike with tag in Northwest side of tree. "Re-blazed" #5
16"-14" Twin Maple S31°W 42.42' Set spike with tag in Easterly side of tree. #6
6" Maple N42°W 40.48' Set spike and tag in West side of tree.

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996
Norman L. Ochs, County Representative.

