

**SURVEY &  
REMONUMENTATION**

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970'00 FEB 28 PM 1 17.

**SECTION**

*Linda M. Brown*

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 14N R 13W T 14N R 14W T 15N R 14W T 15N R 13W	<del>A-1</del> M-1 ✓ <del>M-13</del> <del>A-13</del>
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

354

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on October 9, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Northwest Corner, Section 6, Lincoln Township, Newaygo County, Michigan.  
Northeast Corner, Section 1, Denver Township, Newaygo County, Michigan.  
Southeast Corner, Section 36, Beaver Township, Newaygo County, Michigan.  
Southwest Corner, Section 31, Merrill Township, Newaygo County, Michigan.

	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Mullett and Brookfield 1838  
9" Cedar (no bearing given) 16 Links (10.56')#1  
16" Hemlock N40°E 35 Links (23.1')#2

Norman C. Caldwell R.L.S. #12018  
LCRC #1124 July 1991  
Placed 36" x 30" with brass cap aluminum monument.  
Centerline of old two track road 3 feet below surface.  
8" Maple S48°W 47.45' #3  
6" Maple N56°E 39.30' #4  
6" Maple S87°E 9.80' #5  
Carsonite Witness Post West 7.7' #6

William M. Jacques (County Surveyor)  
Book 44 Page 17 November 3, 1913  
Found old stake.

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found brass cap on top of rod in the centerline of the North and South trail road. Woven fence on ground going West is 33 feet North. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Accepted brass cap on top of rod as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

16" Maple S50°W 47.59' Found spike in Northwest side of tree. #3  
10" Maple N60°E 39.37' Found spike in Southeast side of tree. #4  
8" Maple S86°E 9.86' Found dock spike in South side of tree. #5  
Carsonite Witness Post N85°W 7.69' #6  
6" diameter by 4 1/2" Steel Post N30°W 40.55'

Signed by Norman L. Ochs Date October 22, 1999

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 16, 1999  
Norman L. Ochs, County Representative.

Revised May 14, 1975  
Revised Jan., 1983

*N.L.O.*

